




Daikin Altherma Monobloc Schematics



EDLA Low Capacity



EDLA High Capacity

Table of contents

Introduction	2	EDLA High Capacity Monobloc	54
EDLA Low Capacity Monobloc	3	ST 202: DHW only	54
ST 102: DHW only	3	ST 203: Radiators only	57
ST 103: Radiators only	6	ST 204: UFH only	60
ST 104: UFH only	9	ST 205: DHW & Radiators	63
ST 105: DHW & Radiators	12	ST 206: DHW & UFH (3rd party controls)	66
ST 106: DHW & UFH (3rd party controls)	15	ST 213: DHW, Radiators & UFH (3rd party controls)	69
ST 107: Radiators & UFH (3rd party controls)	18	ST 215: Radiators & UFH (3rd party controls)	71
ST 108: DHW, Radiators & UFH (3rd party controls)	21	ST 217: DHW & 2 Zone Radiators (3rd party cylinder)	74
ST 114: DHW & Radiators (3rd party cylinder)	24	ST 261: Cylinder & DHW (3rd party controls)	77
ST 119: DHW & 2 Zone Radiators (3rd party controls)	27	ST 262: DHW (3rd party cylinder)	80
ST 160: DHW (3rd party cylinder)	30	ST 263: DHW & UFH (3rd party cylinder)	83
ST 162: DHW & UFH (3rd party cylinder)	33	ST 266: DHW, Radiators & UFH (3rd party controls)	86
ST 165: DHW, Radiators & UFH (3rd party cylinder/controls)	37	ST 268: DHW, 2 Zone Radiators & UFH (3rd party cylinder)	89
ST 167: DHW, 2 Zone Radiators (3rd party cylinder)	39	ST 279: DHW, 2 Zone Radiators (Pre-Plumbed Cylinder & 3rd party controls)	92
ST 169: DHW, 2 Zone Radiators (Pre-Plumbed Cylinder & 3rd party controls)	42	ST 282: DHW & Radiators (Pre-Plumbed Cylinder)	95
ST 171: DHW & Radiators (Pre-Plumbed Cylinder)	45	ST 283: DHW & UFH (Pre-plumbed Cylinder)	98
ST 172: DHW & UFH (Pre-plumbed Cylinder)	48	ST 286: DHW, Radiators & UFH (Pre-plumbed Cylinder & 3rd party Controls)	101
ST 173: DHW, Radiators & UFH (Pre-plumbed Cylinder & 3rd party Controls)	51	Warranty and maintenance	103

Daikin Altherma Monobloc

Low capacity 4-8 and high capacity 9-16

The Daikin Altherma 3 Monobloc is an outdoor only unit including an enclosed refrigerant circuit. It is an all-in-one concept with all key hydraulics included in a single unit, such as the pump, flow sensor, and water pressure sensor. The system requires no indoor unit, only a user interface and a stand-alone domestic hot water tank.


The high capacity models (9-16) are available with an integrated backup heater, whereas the low capacity models (4-8) do not have an inbuilt backup heater. The backup heater will be available as an optional accessory. Also available as an option for all models is a wiring centre which offers a central wiring connection for all components installed inside the house.




Combination table

Outdoor	EB/DLA04-08E Low capacity monobloc		E(D/B)LA9-16D High capacity monobloc	
	 4-8 kW		 9-16 kW	
Indoor	N/A	N/A	N/A	N/A
DHW Cylinder	SB.EKHWSU Hot water cylinder		or	UK.PPC/R32 Pre-Plumbed R-32 Cylinder
				

ST 102: EDLA Low Capacity Monobloc - DHW Only - Mechanical




ST 102: EDLA Low Capacity Monobloc - DHW Only - **Electrical**




ST 102: EDLA Low Capacity Monobloc - DHW Only - Key Data

1	2	3	4	5	6	7	8																																																																																																														
Drawing Number: ST-102 (3 of 3)	Scale: NTS@ A3	Revision: P3	 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																																																
FIRST FIX			INSTALLATION PHASE			PRE-COMMISSIONING																																																																																																															
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE <table border="1"> <thead> <tr> <th>EQUIPMENT</th><th>EDLA04EV3</th><th>EDLA06EV3</th><th>EDLA08EV3</th></tr> </thead> <tbody> <tr> <td>PRIMARY PIPEWORK (mm)</td><td colspan="3">MINIMUM 28</td></tr> <tr> <td>FLOW RATE (l/min) CENTRAL HEATING</td><td>13.2</td><td>17.2</td><td>22.4</td></tr> <tr> <td>MINIMUM WATER VOLUME (Litres)</td><td colspan="3">SEE TABLE 3</td></tr> <tr> <td>MAX CURRENT (A)</td><td colspan="2">19.9</td><td>24</td></tr> <tr> <td>FUSE (A)</td><td colspan="2">20</td><td>25</td></tr> <tr> <td>MAINS FOR DHW BSH (K3M)</td><td colspan="3">230v</td></tr> <tr> <td>MAX CURRENT (A) DHW BSH</td><td colspan="3">13.04</td></tr> <tr> <td>FUSE (A)</td><td colspan="3">16</td></tr> <tr> <td>MINIMUM CABLE (mm²) FOR MMI</td><td colspan="3">1.5</td></tr> <tr> <td>MAXIMUM DISTANCE TO TANK (m)</td><td colspan="3">10</td></tr> <tr> <td>MAXIMUM LEVEL DIFFERENCE (m)</td><td colspan="3">5</td></tr> <tr> <td>HEIGHT (mm)</td><td colspan="3">770</td></tr> <tr> <td>WIDTH (mm)</td><td colspan="3">1250</td></tr> <tr> <td>DEPTH (mm)</td><td colspan="3">362</td></tr> <tr> <td>WEIGHT EMPTY (kg)</td><td colspan="3">88</td></tr> <tr> <td>WEIGHT FULL (kg)</td><td colspan="3">96</td></tr> </tbody> </table>			EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3	PRIMARY PIPEWORK (mm)	MINIMUM 28			FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4	MINIMUM WATER VOLUME (Litres)	SEE TABLE 3			MAX CURRENT (A)	19.9		24	FUSE (A)	20		25	MAINS FOR DHW BSH (K3M)	230v			MAX CURRENT (A) DHW BSH	13.04			FUSE (A)	16			MINIMUM CABLE (mm²) FOR MMI	1.5			MAXIMUM DISTANCE TO TANK (m)	10			MAXIMUM LEVEL DIFFERENCE (m)	5			HEIGHT (mm)	770			WIDTH (mm)	1250			DEPTH (mm)	362			WEIGHT EMPTY (kg)	88			WEIGHT FULL (kg)	96			TABLE 2 - INSULATION THICKNESS <table border="1"> <thead> <tr> <th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr> </thead> <tbody> <tr> <td><20</td><td>19</td></tr> <tr> <td>20-30</td><td>32</td></tr> <tr> <td>30-40</td><td>40</td></tr> <tr> <td>40-50</td><td>50</td></tr> </tbody> </table>			PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	CHECKLIST BEFORE COMMISSIONING AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table border="1"> <tbody> <tr> <td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr> <tr> <td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr> <tr> <td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr> <tr> <td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr> <tr> <td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr> <tr> <td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr> <tr> <td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr> <tr> <td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr> <tr> <td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr> <tr> <td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr> <tr> <td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr> <tr> <td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr> <tr> <td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr> <tr> <td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr> <tr> <td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr> <tr> <td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr> </tbody> </table>			YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3																																																																																																																		
PRIMARY PIPEWORK (mm)	MINIMUM 28																																																																																																																				
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4																																																																																																																		
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3																																																																																																																				
MAX CURRENT (A)	19.9		24																																																																																																																		
FUSE (A)	20		25																																																																																																																		
MAINS FOR DHW BSH (K3M)	230v																																																																																																																				
MAX CURRENT (A) DHW BSH	13.04																																																																																																																				
FUSE (A)	16																																																																																																																				
MINIMUM CABLE (mm²) FOR MMI	1.5																																																																																																																				
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																																				
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																																				
HEIGHT (mm)	770																																																																																																																				
WIDTH (mm)	1250																																																																																																																				
DEPTH (mm)	362																																																																																																																				
WEIGHT EMPTY (kg)	88																																																																																																																				
WEIGHT FULL (kg)	96																																																																																																																				
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																																				
<20	19																																																																																																																				
20-30	32																																																																																																																				
30-40	40																																																																																																																				
40-50	50																																																																																																																				
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																																				
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																																				
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																																				
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																																				
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																																				
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																																				
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																																				
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																																				
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																																				
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																																				
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																																				
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																																				
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																																				
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																																				
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																				
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																																				
TABLE 3 - MINIMUM WATER VOLUME <table border="1"> <thead> <tr> <th>IF</th><th>THEN THE MINIMUM WATER VOLUME IS...</th></tr> </thead> <tbody> <tr> <td>HEATING/DEFROST OPERATION AND...</td><td></td></tr> <tr> <td>PREHEATING ON THE TANK IS POSSIBLE</td><td>0ltrs</td></tr> <tr> <td>PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT</td><td>10ltrs</td></tr> <tr> <td>PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...</td><td></td></tr> <tr> <td>THE RETURN FLOW TEMPERATURE IS >15°C</td><td>20ltrs</td></tr> <tr> <td>THE RETURN FLOW TEMPERATURE IS ,15°C</td><td>50ltrs</td></tr> </tbody> </table>			IF	THEN THE MINIMUM WATER VOLUME IS...	HEATING/DEFROST OPERATION AND...		PREHEATING ON THE TANK IS POSSIBLE	0ltrs	PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs	PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...		THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs	THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs	 DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC		 UNBOXING SMALL MONOBLOC		 3-WAY VALVE EXPLAINED																																																																																																
IF	THEN THE MINIMUM WATER VOLUME IS...																																																																																																																				
HEATING/DEFROST OPERATION AND...																																																																																																																					
PREHEATING ON THE TANK IS POSSIBLE	0ltrs																																																																																																																				
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs																																																																																																																				
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...																																																																																																																					
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs																																																																																																																				
THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs																																																																																																																				
			 MMI USER GUIDE		 SMALL MONOBLOC PRODUCT VIDEO		CHECKLIST DURING COMMISSIONING <table border="1"> <tbody> <tr> <td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr> <tr> <td></td><td>TO PERFORM AN AIR PURGE.</td></tr> <tr> <td></td><td>TO PERFORM A TEST RUN.</td></tr> <tr> <td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr> <tr> <td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr> </tbody> </table>			THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																			
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																				
	TO PERFORM AN AIR PURGE.																																																																																																																				
	TO PERFORM A TEST RUN.																																																																																																																				
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																																																				
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																																				
NOTES - AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. - IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT. - ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. - ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. - EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. - FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																																																					
P3 PHASE 2 UPDATES <table border="1"> <thead> <tr> <th>Description</th><th>Engineer</th><th>Checked</th><th>Date</th></tr> </thead> <tbody> <tr> <td>P3 PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>24.09.24</td></tr> <tr> <td>P2 FLOW SWITCH REFERENCE UPDATE</td><td>PBM</td><td>SB</td><td>07.06.24</td></tr> <tr> <td>P1 PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>12.05.23</td></tr> </tbody> </table>		Description	Engineer	Checked	Date	P3 PHASE 2 UPDATES	PBM	SB	24.09.24	P2 FLOW SWITCH REFERENCE UPDATE	PBM	SB	07.06.24	P1 PRELIMINARY ISSUE	RB	SB	12.05.23	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: Small MonoBloc EDLA 04-08 (1 PHASE) DOMESTIC HOT WATER		Drawing Status: PRELIMINARY		Telephone																																																																																													
Description	Engineer	Checked	Date																																																																																																																		
P3 PHASE 2 UPDATES	PBM	SB	24.09.24																																																																																																																		
P2 FLOW SWITCH REFERENCE UPDATE	PBM	SB	07.06.24																																																																																																																		
P1 PRELIMINARY ISSUE	RB	SB	12.05.23																																																																																																																		

ST 103: EDLA Low Capacity Monobloc - Radiators Only - Mechanical



ST 103: EDLA Low Capacity Monobloc - Radiators Only - Electrical



ST 103: EDLA Low Capacity Monobloc - Radiators Only - Key Data

1

2

3

4

5

6

7

8

Drawing Number:
ST-103 (3 of 3)

Scale:
NTS@ A3

Revision:
P3

• SEE PAGE 1 FOR MECHANICAL SET UP.
• SEE PAGE 2 FOR DETAILED WIRING.
• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING
• OPTIONAL FOR HEAT METERS
• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

FIRST FIX

INSTALLATION PHASE

PRE-COMMISSIONING

TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9	24	
FUSE (A)	20	25	
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

TABLE 2 - INSULATION THICKNESS

PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)
<20	19
20-30	32
30-40	40
40-50	50

TABLE 3 - MINIMUM WATER VOLUME

IF	THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...	
PREHEATING ON THE TANK IS POSSIBLE	0ltrs
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...	
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs
THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs

DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC

UNBOXING SMALL MONOBLOC

MMI USER GUIDE

3-WAY VALVE EXPLAINED

SMALL MONOBLOC PRODUCT VIDEO

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.

• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.

• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.

• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.

• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.

• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)

P3

PHASE 2 UPDATES

PBM

SB

24.09.24

P2

FLOW SWITCH REFERENCE UPDATE

PBM

SB

07.06.24

P1

PRELIMINARY ISSUE

RB

SB

12.05.23

Rev

Description

Engineer

Checked

Date

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.

2. WORK TO FIGURED DIMENSIONS ONLY.

3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.

Drawing:

Small MonoBloc
EDLA 04-08 (1 PHASE)
RADIATORS

Drawing Status:

PRELIMINARY

Telephone: 01932 879 070 (Option 1)
Email: heating@daikin.co.uk

DAIKIN

altherma

1

2

3

4

5


6

7


8

8

ST 104: EDLA Low Capacity Monobloc - UFH Only - Mechanical



ST 104: EDLA Low Capacity Monobloc - UFH Only - **Electrical**



ST 104: EDLA Low Capacity Monobloc - UFH Only - Key data

1

Drawing Number:
ST-104 (3 of 3)

2

Scale:
NTS@ A3

3

Revision:
P4

4

⚠

• SEE PAGE 1 FOR MECHANICAL SET UP.
• SEE PAGE 2 FOR DETAILED WIRING.
• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING
• OPTIONAL FOR HEAT METERS
• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

5

6

7

8

FIRST FIX

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9		24
FUSE (A)	20		25
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

IF		THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...		
PREHEATING ON THE TANK IS POSSIBLE PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...		0ltrs
		10ltrs
	THE RETURN FLOW TEMPERATURE IS >15°C THE RETURN FLOW TEMPERATURE IS ,15°C	
		50ltrs

INSTALLATION PHASE

PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)
<20	19
20-30	32
30-40	40
40-50	50



DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC



UNBOXING SMALL MONOBLOC



MMI USER GUIDE



3-WAY VALVE EXPLAINED



SMALL MONOBLOC PRODUCT VIDEO

PRE-COMMISSIONING

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

- AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.
- IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.
- ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.
- ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.
- EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.
- FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)**

					1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.	Drawing: Small MonoBloc EDLA 04-08 (1 PHASE) UNDERFLOOR HEATING	Drawing Status: PRELIMINARY	Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk	
P4	PHASE 2 UPDATES	PBM	SB	24.09.24					
P3	MIXING VALVE UPDATED	PBM	SB	25.03.24					
P2	WIRING UPDATED	PBM	SB	7.09.23					
P1	PRELIMINARY ISSUE	PBM	SB	12.05.23					
Rev	Description	Engineer	Checked	Date					

1

2

3

4


5

6


7

8

ST 105: EDLA Low Capacity Monobloc - DHW & Radiators - Mechanical




ST 105: EDLA Low Capacity Monobloc - DHW & Radiators - **Electrical**




ST 105: EDLA Low Capacity Monobloc - DHW & Radiators - Key data

1		2		3		4		5		6		7		8																																																																																																																	
Drawing Number: ST-105 (3 of 3)		Scale: NTS@ A3		Revision: P4		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																																																							
FIRST FIX						INSTALLATION PHASE						PRE-COMMISSIONING																																																																																																																			
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE						TABLE 2 - INSULATION THICKNESS						CHECKLIST BEFORE COMMISSIONING																																																																																																																			
<table><tr><th>EQUIPMENT</th><th>EDLA04EV3</th><th>EDLA06EV3</th><th>EDLA08EV3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td colspan="3">MINIMUM 28</td></tr><tr><td>FLOW RATE (l/min) CENTRAL HEATING</td><td>13.2</td><td>17.2</td><td>22.4</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td colspan="3">SEE TABLE 3</td></tr><tr><td>MAX CURRENT (A)</td><td>19.9</td><td colspan="2">24</td></tr><tr><td>FUSE (A)</td><td>20</td><td colspan="2">25</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td colspan="3">230v</td></tr><tr><td>MAX CURRENT (A) DHW BSH</td><td colspan="3">13.04</td></tr><tr><td>FUSE (A)</td><td colspan="3">16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td colspan="3">1.5</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td colspan="3">10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td colspan="3">5</td></tr><tr><td>HEIGHT (mm)</td><td colspan="3">770</td></tr><tr><td>WIDTH (mm)</td><td colspan="3">1250</td></tr><tr><td>DEPTH (mm)</td><td colspan="3">362</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td colspan="3">88</td></tr><tr><td>WEIGHT FULL (kg)</td><td colspan="3">96</td></tr></table>						EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3	PRIMARY PIPEWORK (mm)	MINIMUM 28			FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4	MINIMUM WATER VOLUME (Litres)	SEE TABLE 3			MAX CURRENT (A)	19.9	24		FUSE (A)	20	25		MAINS FOR DHW BSH (K3M)	230v			MAX CURRENT (A) DHW BSH	13.04			FUSE (A)	16			MINIMUM CABLE (mm²) FOR MMI	1.5			MAXIMUM DISTANCE TO TANK (m)	10			MAXIMUM LEVEL DIFFERENCE (m)	5			HEIGHT (mm)	770			WIDTH (mm)	1250			DEPTH (mm)	362			WEIGHT EMPTY (kg)	88			WEIGHT FULL (kg)	96			<table><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>						PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	<u>CHECKLIST BEFORE COMMISSIONING</u> AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>							YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3																																																																																																																												
PRIMARY PIPEWORK (mm)	MINIMUM 28																																																																																																																														
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4																																																																																																																												
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3																																																																																																																														
MAX CURRENT (A)	19.9	24																																																																																																																													
FUSE (A)	20	25																																																																																																																													
MAINS FOR DHW BSH (K3M)	230v																																																																																																																														
MAX CURRENT (A) DHW BSH	13.04																																																																																																																														
FUSE (A)	16																																																																																																																														
MINIMUM CABLE (mm²) FOR MMI	1.5																																																																																																																														
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																																														
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																																														
HEIGHT (mm)	770																																																																																																																														
WIDTH (mm)	1250																																																																																																																														
DEPTH (mm)	362																																																																																																																														
WEIGHT EMPTY (kg)	88																																																																																																																														
WEIGHT FULL (kg)	96																																																																																																																														
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																																														
<20	19																																																																																																																														
20-30	32																																																																																																																														
30-40	40																																																																																																																														
40-50	50																																																																																																																														
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																																														
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																																														
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																																														
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																																														
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																																														
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																																														
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																																														
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																																														
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																																														
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																																														
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																																														
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																																														
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																																														
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																																														
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																														
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																																														
TABLE 3 - MINIMUM WATER VOLUME						DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC						3-WAY VALVE EXPLAINED																																																																																																																			
<table><tr><th colspan="2">IF</th><th>THEN THE MINIMUM WATER VOLUME IS...</th></tr><tr><td colspan="3">HEATING/DEFROST OPERATION AND...</td></tr><tr><td>PREHEATING ON THE TANK IS POSSIBLE</td><td></td><td>0ltrs</td></tr><tr><td>PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT</td><td></td><td>10ltrs</td></tr><tr><td>PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...</td><td></td><td></td></tr><tr><td>THE RETURN FLOW TEMPERATURE IS >15°C</td><td></td><td>20ltrs</td></tr><tr><td>THE RETURN FLOW TEMPERATURE IS , 15°C</td><td></td><td>50ltrs</td></tr></table>						IF		THEN THE MINIMUM WATER VOLUME IS...	HEATING/DEFROST OPERATION AND...			PREHEATING ON THE TANK IS POSSIBLE		0ltrs	PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT		10ltrs	PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...			THE RETURN FLOW TEMPERATURE IS >15°C		20ltrs	THE RETURN FLOW TEMPERATURE IS , 15°C		50ltrs	UNBOXING SMALL MONOBLOC						SMALL MONOBLOC PRODUCT VIDEO																																																																																														
IF		THEN THE MINIMUM WATER VOLUME IS...																																																																																																																													
HEATING/DEFROST OPERATION AND...																																																																																																																															
PREHEATING ON THE TANK IS POSSIBLE		0ltrs																																																																																																																													
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT		10ltrs																																																																																																																													
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...																																																																																																																															
THE RETURN FLOW TEMPERATURE IS >15°C		20ltrs																																																																																																																													
THE RETURN FLOW TEMPERATURE IS , 15°C		50ltrs																																																																																																																													
MMI USER GUIDE																																																																																																																															
NOTES												CHECKLIST DURING COMMISSIONING																																																																																																																			
- AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. - IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT. - ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. - ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. - EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. - FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)												<table><tr><td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>TO PERFORM AN AIR PURGE.</td></tr><tr><td></td><td>TO PERFORM A TEST RUN.</td></tr><tr><td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr><tr><td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr></table>							THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																				
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																														
	TO PERFORM AN AIR PURGE.																																																																																																																														
	TO PERFORM A TEST RUN.																																																																																																																														
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																																																														
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																																														
P4 PHASE 2 UPDATES						Drawing: Small MonoBloc						Drawing Status: PRELIMINARY						Telephone: 01932 879 070 (Option 1)																																																																																																													
P3 MIXING VALVE UPDATED						EDLA 04-08 (1 PHASE)												Email: heating@daikin.co.uk																																																																																																													
P2 WIRING UPDATED						DHW & RADIATORS																																																																																																																									
P1 PRELIMINARY ISSUE																																																																																																																															
Rev Description						Engineer Checked Date																																																																																																																									
1		2		3		4		5		6		7		8																																																																																																																	

ST 106: EDLA Low Capacity Monobloc - Third Party Controls, DHW & UFH - **Mechanical**




ST 106: EDLA Low Capacity Monobloc - Third Party Controls, DHW & UFH - **Electrical**




ST 106: EDLA Low Capacity Monobloc - Third Party Controls, DHW & UFH - Key Data

1		2		3		4		5		6		7		8																																																																																																																							
Drawing Number: ST-106 (3 of 3)		Scale: NTS@ A3		Revision: P3		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																																																													
FIRST FIX						INSTALLATION PHASE						PRE-COMMISSIONING																																																																																																																									
<table><tr><th colspan="4">TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA04EV3</th><th>EDLA06EV3</th><th>EDLA08EV3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td colspan="3">MINIMUM 28</td></tr><tr><td>FLOW RATE (l/min) CENTRAL HEATING</td><td>13.2</td><td>17.2</td><td>22.4</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td colspan="3">SEE TABLE 3</td></tr><tr><td>MAX CURRENT (A)</td><td colspan="2">19.9</td><td>24</td></tr><tr><td>FUSE (A)</td><td colspan="2">20</td><td>25</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td colspan="3">230v</td></tr><tr><td>MAX CURRENT (A) DHW BSH</td><td colspan="3">13.04</td></tr><tr><td>FUSE (A)</td><td colspan="3">16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td colspan="3">1.5</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td colspan="3">10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td colspan="3">5</td></tr><tr><td>HEIGHT (mm)</td><td colspan="3">770</td></tr><tr><td>WIDTH (mm)</td><td colspan="3">1250</td></tr><tr><td>DEPTH (mm)</td><td colspan="3">362</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td colspan="3">88</td></tr><tr><td>WEIGHT FULL (kg)</td><td colspan="3">96</td></tr></table>						TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE				EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3	PRIMARY PIPEWORK (mm)	MINIMUM 28			FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4	MINIMUM WATER VOLUME (Litres)	SEE TABLE 3			MAX CURRENT (A)	19.9		24	FUSE (A)	20		25	MAINS FOR DHW BSH (K3M)	230v			MAX CURRENT (A) DHW BSH	13.04			FUSE (A)	16			MINIMUM CABLE (mm²) FOR MMI	1.5			MAXIMUM DISTANCE TO TANK (m)	10			MAXIMUM LEVEL DIFFERENCE (m)	5			HEIGHT (mm)	770			WIDTH (mm)	1250			DEPTH (mm)	362			WEIGHT EMPTY (kg)	88			WEIGHT FULL (kg)	96			<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>						TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	<u>CHECKLIST BEFORE COMMISSIONING</u> AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>							YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE																																																																																																																																					
EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3																																																																																																																																		
PRIMARY PIPEWORK (mm)	MINIMUM 28																																																																																																																																				
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4																																																																																																																																		
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3																																																																																																																																				
MAX CURRENT (A)	19.9		24																																																																																																																																		
FUSE (A)	20		25																																																																																																																																		
MAINS FOR DHW BSH (K3M)	230v																																																																																																																																				
MAX CURRENT (A) DHW BSH	13.04																																																																																																																																				
FUSE (A)	16																																																																																																																																				
MINIMUM CABLE (mm²) FOR MMI	1.5																																																																																																																																				
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																																																				
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																																																				
HEIGHT (mm)	770																																																																																																																																				
WIDTH (mm)	1250																																																																																																																																				
DEPTH (mm)	362																																																																																																																																				
WEIGHT EMPTY (kg)	88																																																																																																																																				
WEIGHT FULL (kg)	96																																																																																																																																				
TABLE 2 - INSULATION THICKNESS																																																																																																																																					
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																																																				
<20	19																																																																																																																																				
20-30	32																																																																																																																																				
30-40	40																																																																																																																																				
40-50	50																																																																																																																																				
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																																																				
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																																																				
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																																																				
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																																																				
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																																																				
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																																																				
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																																																				
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																																																				
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																																																				
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																																																				
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																																																				
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																																																				
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																																																				
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																																																				
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																																				
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																																																				
<table><tr><th colspan="2">TABLE 3 - MINIMUM WATER VOLUME</th></tr><tr><th>IF</th><th>THEN THE MINIMUM WATER VOLUME IS...</th></tr><tr><td colspan="2">HEATING/DEFROST OPERATION AND...</td></tr><tr><td>PREHEATING ON THE TANK IS POSSIBLE</td><td>0ltrs</td></tr><tr><td>PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT</td><td>10ltrs</td></tr><tr><td>PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...</td><td></td></tr><tr><td>THE RETURN FLOW TEMPERATURE IS >15°C</td><td>20ltrs</td></tr><tr><td>THE RETURN FLOW TEMPERATURE IS ,15°C</td><td>50ltrs</td></tr></table>						TABLE 3 - MINIMUM WATER VOLUME		IF	THEN THE MINIMUM WATER VOLUME IS...	HEATING/DEFROST OPERATION AND...		PREHEATING ON THE TANK IS POSSIBLE	0ltrs	PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs	PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...		THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs	THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs	DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC UNBOXING SMALL MONOBLOC MMI USER GUIDE 3-WAY VALVE EXPLAINED SMALL MONOBLOC PRODUCT VIDEO																																																																																																															
TABLE 3 - MINIMUM WATER VOLUME																																																																																																																																					
IF	THEN THE MINIMUM WATER VOLUME IS...																																																																																																																																				
HEATING/DEFROST OPERATION AND...																																																																																																																																					
PREHEATING ON THE TANK IS POSSIBLE	0ltrs																																																																																																																																				
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs																																																																																																																																				
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...																																																																																																																																					
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs																																																																																																																																				
THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs																																																																																																																																				
<u>NOTES</u> • AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. • IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT. • ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. • ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. • EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. • FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																																																																					
<table><tr><td></td><td></td><td></td><td></td><td></td></tr><tr><td>P3</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>25.09.24</td></tr><tr><td>P2</td><td>MIXING VALVE UPDATED</td><td>PBM</td><td>SB</td><td>25.03.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>PBM</td><td>SB</td><td>12.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>							P3	PHASE 2 UPDATES	PBM	SB	25.09.24	P2	MIXING VALVE UPDATED	PBM	SB	25.03.24	P1	PRELIMINARY ISSUE	PBM	SB	12.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.		Drawing: Small MonoBloc EDLA 04-08 (1 PHASE)		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																																																				
P3	PHASE 2 UPDATES	PBM	SB	25.09.24																																																																																																																																	
P2	MIXING VALVE UPDATED	PBM	SB	25.03.24																																																																																																																																	
P1	PRELIMINARY ISSUE	PBM	SB	12.05.23																																																																																																																																	
Rev	Description	Engineer	Checked	Date																																																																																																																																	
1		2		3		4		5		6		7		8																																																																																																																							

ST 107: EDLA Low Capacity Monobloc - Third Party Controls, Radiator & UFH - Mechanical




ST 107: EDLA Low Capacity Monobloc - Third Party Controls, Radiator & UFH - **Electrical**




ST 107: EDLA Low Capacity Monobloc - Third Party Controls, Radiator & UFH - Key Data

1		2		3		4		5		6		7		8																																																																																																																							
Drawing Number: ST-107 (3 of 3)		Scale: NTS@ A3		Revision: P3		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																																																													
FIRST FIX						INSTALLATION PHASE						PRE-COMMISSIONING																																																																																																																									
<table><tr><th colspan="4">TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA04EV3</th><th>EDLA06EV3</th><th>EDLA08EV3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td colspan="3">MINIMUM 28</td></tr><tr><td>FLOW RATE (l/min) CENTRAL HEATING</td><td>13.2</td><td>17.2</td><td>22.4</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td colspan="3">SEE TABLE 3</td></tr><tr><td>MAX CURRENT (A)</td><td colspan="2">19.9</td><td>24</td></tr><tr><td>FUSE (A)</td><td colspan="2">20</td><td>25</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td colspan="3">230v</td></tr><tr><td>MAX CURRENT (A) DHW BSH</td><td colspan="3">13.04</td></tr><tr><td>FUSE (A)</td><td colspan="3">16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td colspan="3">1.5</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td colspan="3">10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td colspan="3">5</td></tr><tr><td>HEIGHT (mm)</td><td colspan="3">770</td></tr><tr><td>WIDTH (mm)</td><td colspan="3">1250</td></tr><tr><td>DEPTH (mm)</td><td colspan="3">362</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td colspan="3">88</td></tr><tr><td>WEIGHT FULL (kg)</td><td colspan="3">96</td></tr></table>						TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE				EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3	PRIMARY PIPEWORK (mm)	MINIMUM 28			FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4	MINIMUM WATER VOLUME (Litres)	SEE TABLE 3			MAX CURRENT (A)	19.9		24	FUSE (A)	20		25	MAINS FOR DHW BSH (K3M)	230v			MAX CURRENT (A) DHW BSH	13.04			FUSE (A)	16			MINIMUM CABLE (mm²) FOR MMI	1.5			MAXIMUM DISTANCE TO TANK (m)	10			MAXIMUM LEVEL DIFFERENCE (m)	5			HEIGHT (mm)	770			WIDTH (mm)	1250			DEPTH (mm)	362			WEIGHT EMPTY (kg)	88			WEIGHT FULL (kg)	96			<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>						TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	<u>CHECKLIST BEFORE COMMISSIONING</u> AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>							YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE																																																																																																																																					
EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3																																																																																																																																		
PRIMARY PIPEWORK (mm)	MINIMUM 28																																																																																																																																				
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4																																																																																																																																		
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3																																																																																																																																				
MAX CURRENT (A)	19.9		24																																																																																																																																		
FUSE (A)	20		25																																																																																																																																		
MAINS FOR DHW BSH (K3M)	230v																																																																																																																																				
MAX CURRENT (A) DHW BSH	13.04																																																																																																																																				
FUSE (A)	16																																																																																																																																				
MINIMUM CABLE (mm²) FOR MMI	1.5																																																																																																																																				
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																																																				
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																																																				
HEIGHT (mm)	770																																																																																																																																				
WIDTH (mm)	1250																																																																																																																																				
DEPTH (mm)	362																																																																																																																																				
WEIGHT EMPTY (kg)	88																																																																																																																																				
WEIGHT FULL (kg)	96																																																																																																																																				
TABLE 2 - INSULATION THICKNESS																																																																																																																																					
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																																																				
<20	19																																																																																																																																				
20-30	32																																																																																																																																				
30-40	40																																																																																																																																				
40-50	50																																																																																																																																				
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																																																				
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																																																				
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																																																				
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																																																				
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																																																				
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																																																				
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																																																				
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																																																				
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																																																				
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																																																				
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																																																				
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																																																				
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																																																				
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																																																				
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																																				
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																																																				
<table><tr><th colspan="4">TABLE 3 - MINIMUM WATER VOLUME</th></tr><tr><th colspan="2">IF</th><th colspan="2">THEN THE MINIMUM WATER VOLUME IS...</th></tr><tr><td colspan="4">HEATING/DEFROST OPERATION AND...</td></tr><tr><td></td><td>PREHEATING ON THE TANK IS POSSIBLE</td><td colspan="2">0ltrs</td></tr><tr><td></td><td>PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT</td><td colspan="2">10ltrs</td></tr><tr><td></td><td>PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...</td><td colspan="2"></td></tr><tr><td></td><td>THE RETURN FLOW TEMPERATURE IS >15°C</td><td colspan="2">20ltrs</td></tr><tr><td></td><td>THE RETURN FLOW TEMPERATURE IS ≤15°C</td><td colspan="2">50ltrs</td></tr></table>						TABLE 3 - MINIMUM WATER VOLUME				IF		THEN THE MINIMUM WATER VOLUME IS...		HEATING/DEFROST OPERATION AND...					PREHEATING ON THE TANK IS POSSIBLE	0ltrs			PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs			PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...				THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs			THE RETURN FLOW TEMPERATURE IS ≤15°C	50ltrs		 DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC  UNBOXING SMALL MONOBLOC  MMI USER GUIDE  3-WAY VALVE EXPLAINED  SMALL MONOBLOC PRODUCT VIDEO						<u>CHECKLIST DURING COMMISSIONING</u> <table><tr><td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>TO PERFORM AN AIR PURGE.</td></tr><tr><td></td><td>TO PERFORM A TEST RUN.</td></tr><tr><td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr><tr><td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr></table>							THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																										
TABLE 3 - MINIMUM WATER VOLUME																																																																																																																																					
IF		THEN THE MINIMUM WATER VOLUME IS...																																																																																																																																			
HEATING/DEFROST OPERATION AND...																																																																																																																																					
	PREHEATING ON THE TANK IS POSSIBLE	0ltrs																																																																																																																																			
	PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs																																																																																																																																			
	PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...																																																																																																																																				
	THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs																																																																																																																																			
	THE RETURN FLOW TEMPERATURE IS ≤15°C	50ltrs																																																																																																																																			
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																																				
	TO PERFORM AN AIR PURGE.																																																																																																																																				
	TO PERFORM A TEST RUN.																																																																																																																																				
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																																																																				
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																																																				
NOTES • AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. • IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT. • ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. • ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. • EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. • FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																																																																					
<table><tr><td></td><td></td><td></td><td></td><td></td></tr><tr><td>P3</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>25.09.24</td></tr><tr><td>P2</td><td>MIXING VALVE UPDATED</td><td>PBM</td><td>SB</td><td>25.03.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>PBM</td><td>SB</td><td>27.06.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>										P3	PHASE 2 UPDATES	PBM	SB	25.09.24	P2	MIXING VALVE UPDATED	PBM	SB	25.03.24	P1	PRELIMINARY ISSUE	PBM	SB	27.06.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.			Drawing: Small MonoBloc EDLA 04-08 (1 PHASE)			Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																																															
P3	PHASE 2 UPDATES	PBM	SB	25.09.24																																																																																																																																	
P2	MIXING VALVE UPDATED	PBM	SB	25.03.24																																																																																																																																	
P1	PRELIMINARY ISSUE	PBM	SB	27.06.23																																																																																																																																	
Rev	Description	Engineer	Checked	Date																																																																																																																																	
1		2		3		4		5		6		7		8																																																																																																																							

ST 108: EDLA Low Capacity Monobloc - Third Party Controls, DHW, Radiator & UFH - Mechanical



ST 108: EDLA Low Capacity Monobloc - Third Party Controls, DHW, Radiator & UFH - **Electrical**



ST 108: EDLA Low Capacity Monobloc - Third Party Controls, DHW, Radiator & UFH - Key Data

1

2

3

4

5

6

7

8

Drawing Number:
ST-108 (3 of 3)

Scale:
NTS@ A3

Revision:
P3

• SEE PAGE 1 FOR MECHANICAL SET UP.
• SEE PAGE 2 FOR DETAILED WIRING.
• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING
• OPTIONAL FOR HEAT METERS
• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

FIRST FIX

INSTALLATION PHASE

PRE-COMMISSIONING

TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9	24	
FUSE (A)	20	25	
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

TABLE 2 - INSULATION THICKNESS

PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)
<20	19
20-30	32
30-40	40
40-50	50

TABLE 3 - MINIMUM WATER VOLUME

IF	THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...	
PREHEATING ON THE TANK IS POSSIBLE	0ltrs
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...	
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs
THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs

DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC

UNBOXING SMALL MONOBLOC

MMI USER GUIDE

3-WAY VALVE EXPLAINED

SMALL MONOBLOC PRODUCT VIDEO

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.

• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.

• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.

• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.

• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.

• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)

P3

PHASE 2 UPDATES

PBM

SB

25.09.24

P2

MIXING VALVE UPDATED

PBM

SB

25.03.24

P1

PRELIMINARY ISSUE

PBM

SB

27.06.23

Rev

Description

Engineer

Checked

Date

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.

2. WORK TO FIGURED DIMENSIONS ONLY.

3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.

Drawing:

Small MonoBloc EDLA 04-08 (1 PHASE)

THIRD PARTY CONTROLS

DHW, RADIATOR & UFH

Drawing Status:

PRELIMINARY

Telephone: 01932 879 070 (Option 1)

Email: heating@daikin.co.uk

DAIKIN

altherma

1

2

3

4

5


6

7


8

23

ST 114: EDLA Low Capacity Monobloc - Third Party Cylinder, DHW & Radiators - **Mechanical**



ST 114: EDLA Low Capacity Monobloc - Third Party Cylinder, DHW & Radiators - **Electrical**



ST 114: EDLA Low Capacity Monobloc - Third Party Cylinder, DHW & Radiators - Key Data

1

Drawing Number:
ST-114 (3 of 3)

2

Scale:
NTS@ A3

3

Revision:
P3

4

• SEE PAGE 1 FOR MECHANICAL SET UP.

• SEE PAGE 2 FOR DETAILED WIRING.

• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

5

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING

• OPTIONAL FOR HEAT METERS

• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

6

7

8

1

TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE

EQUIPMENT

EDLA04EV3

EDLA06EV3

EDLA08EV3

PRIMARY PIPEWORK (mm)

MINIMUM 28

FLOW RATE (l/min) CENTRAL HEATING

13.2

17.2

22.4

MINIMUM WATER VOLUME (Litres)

SEE TABLE 3

MAX CURRENT (A)

19.9

24

FUSE (A)

20

25

MAINS FOR DHW BSH (K3M)

230v

MAX CURRENT (A) DHW BSH

13.04

FUSE (A)

16

MINIMUM CABLE (mm²) FOR MMI

1.5

MAXIMUM DISTANCE TO TANK (m)

10

MAXIMUM LEVEL DIFFERENCE (m)

5

HEIGHT (mm)

770

WIDTH (mm)

1250

DEPTH (mm)

362

WEIGHT EMPTY (kg)

88

WEIGHT FULL (kg)

96

TABLE 3 - MINIMUM WATER VOLUME

IF

THEN THE MINIMUM WATER VOLUME IS...

HEATING/DEFROST OPERATION AND...

PREHEATING ON THE TANK IS POSSIBLE

0ltrs

PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT

10ltrs

PREHEATING THE TANK IS NOT POSSIBLE. THERE IS NO BACK UP HEATER, AND...

THE RETURN FLOW TEMPERATURE IS >15°C

20ltrs

THE RETURN FLOW TEMPERATURE IS ,15°C

50ltrs

DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC

UNBOXING SMALL MONOBLOC

MMI USER GUIDE

3-WAY VALVE EXPLAINED

SMALL MONOBLOC PRODUCT VIDEO

DAIKIN

altherma

Telephone: 01932 879 070 (Option 1)

Email: heating@daikin.co.uk

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

1


2

3


4

5

ST 119: EDLA Low Capacity Monobloc - Third Party Controls, DHW & 2 Zone Radiator Circuit - **Mechanical**



ST 119: EDLA Low Capacity Monobloc - Third Party Controls, DHW & 2 Zone Radiator Circuit - **Electrical**



ST 119: EDLA Low Capacity Monobloc - Third Party Controls, DHW & 2 Zone Radiator Circuit - Key Data

1

Drawing Number:
ST-119 (3 of 3)

2

Scale:
NTS@ A3

3

Revision:
P2

• SEE PAGE 1 FOR MECHANICAL SET UP.

• SEE PAGE 2 FOR DETAILED WIRING.

• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

4

5

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING

• OPTIONAL FOR HEAT METERS

• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

6

7

8

FIRST FIX

TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9	24	
FUSE (A)	20	25	
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

TABLE 3 - MINIMUM WATER VOLUME

IF		THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...		
PREHEATING ON THE TANK IS POSSIBLE		0ltrs
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT		10ltrs
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...		
THE RETURN FLOW TEMPERATURE IS >15°C		20ltrs
THE RETURN FLOW TEMPERATURE IS ,15°C		50ltrs

DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC

UNBOXING SMALL MONOBLOC

3-WAY VALVE EXPLAINED

MMI USER GUIDE

SMALL MONOBLOC PRODUCT VIDEO

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.

• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.

• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.

• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.

• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.

• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)

P2

PHASE 2 UPDATES

PBM

SB

25.09.24

P1

PRELIMINARY ISSUE

RB

SB

16.05.23

Rev

Description

Engineer

Checked

Date

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.

2. WORK TO FIGURED DIMENSIONS ONLY.

3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.

Drawing:

Small MonoBloc EDLA 04-08 (1 PHASE)

THIRD PARTY CONTROLS

DHW & 2 ZONE RADIATOR CIRCUITS

Drawing Status:

PRELIMINARY

Telephone: 01932 879 070 (Option 1)

Email: heating@daikin.co.uk

DAIKIN

altherma

1

2

3

4


5

6


7

8

ST 160: EDLA Low Capacity Monobloc - Third Party Cylinder & DHW - **Mechanical**



ST 160: EDLA Low Capacity Monobloc - Third Party Cylinder & DHW - **Electrical**



ST 160: EDLA Low Capacity Monobloc - Third Party Cylinder & DHW - Key Data

1

2

3

4

5

6

7

8

Drawing Number:
ST-160 (3 of 3)

Scale:
NTS@ A3

Revision:
P3

• SEE PAGE 1 FOR MECHANICAL SET UP.
• SEE PAGE 2 FOR DETAILED WIRING.
• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING
• OPTIONAL FOR HEAT METERS
• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

FIRST FIX

INSTALLATION PHASE

PRE-COMMISSIONING

TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9	24	
FUSE (A)	20	25	
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

TABLE 2 - INSULATION THICKNESS

PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)
<20	19
20-30	32
30-40	40
40-50	50

THIRD PARTY TANK TECHNICAL REQUIREMENTS

The specifier must take care to ensure that the cylinder is suitable for the heat pump application.
Where a third party cylinder has been specified, Daikin strongly recommend that the specifier/installer checks the following points:

- Cylinder has a dry pocket to accommodate the Daikin cylinder sensor (Diameter 8mm, minimum recommend depth 28mm).
- The heat exchanger coil is suitably dimensioned for the heat input from the relevant heat pump.
- The immersion heater is positioned above the indirect heating coil.
- Insulation of tank and the standing heat loss meets the requirements of the current building regulations.
- Cylinder has the following approvals: G3, Water Regulations, Building Regulations, CE marked.

TABLE 3 - MINIMUM WATER VOLUME

IF		THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...		
PREHEATING ON THE TANK IS POSSIBLE PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...		0ltrs
		10ltrs
THE RETURN FLOW TEMPERATURE IS >15°C THE RETURN FLOW TEMPERATURE IS ,15°C		20ltrs
		50ltrs

DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC

UNBOXING SMALL MONOBLOC

MMI USER GUIDE

3-WAY VALVE EXPLAINED

SMALL MONOBLOC PRODUCT VIDEO

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	((IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

- AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.
- IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.
- ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.
- ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.
- EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.
- FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)

P3 PHASE 2 UPDATES

P2 FLOW SWITCH REFERENCE UPDATE

P1 PRELIMINARY ISSUE

Rev

Description

Engineer

Checked

Date

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.

2. WORK TO FIGURED DIMENSIONS ONLY.

3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.

Drawing:

Small MonoBloc EDLA 04-08 (1 PHASE)

THIRD PARTY CYLINDER,

DOMESTIC HOT WATER

Drawing Status:

PRELIMINARY


Telephone: 01932 879 070 (Option 1)

Email: heating@daikin.co.uk


DAIKIN

altherma

ST 162: EDLA Low Capacity Monobloc - Third Party Cylinder, DHW & UFH - Mechanical



ST 162: EDLA Low Capacity Monobloc - Third Party Cylinder, DHW & UFH - **Electrical**



ST 162: EDLA Low Capacity Monobloc - Third Party Cylinder, DHW & UFH - Key Data

1

2

3

4

5

6

7

8

Drawing Number:
ST-162 (3 of 3)

Scale:
NTS@ A3

Revision:
P3

• SEE PAGE 1 FOR MECHANICAL SET UP.
• SEE PAGE 2 FOR DETAILED WIRING.
• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

• DPTD RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING
• OPTIONAL FOR HEAT METERS
• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

FIRST FIX

INSTALLATION PHASE

PRE-COMMISSIONING

TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9	24	
FUSE (A)	20	25	
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

TABLE 3 - MINIMUM WATER VOLUME

IF	THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...	
PREHEATING ON THE TANK IS POSSIBLE	0ltrs
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...	
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs
THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs

TABLE 2 - INSULATION THICKNESS

PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)
<20	19
20-30	32
30-40	40
40-50	50

THIRD PARTY TANK TECHNICAL REQUIREMENTS

The specifier must take care to ensure that the cylinder is suitable for the heat pump application.

Where a third party cylinder has been specified, Daikin strongly recommend that the specifier/installer checks the following points:

- Cylinder has a dry pocket to accommodate the Daikin cylinder sensor (Diameter 8mm, minimum recommend depth 28mm).
- The heat exchanger coil is suitably dimensioned for the heat input from the relevant heat pump.
- The immersion heater is positioned above the indirect heating coil.
- Insulation of tank and the standing heat loss meets the requirements of the current building regulations.
- Cylinder has the following approvals: G3, Water Regulations, Building Regulations, CE marked.

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

- AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.
- IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.
- ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.
- ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.
- EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.
- FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)

P3

PHASE 2 UPDATES

PBM

SB

25.09.24

P2

FLOW SWITCH REFERENCE UPDATE

PBM

SB

07.06.24

P1

PRELIMINARY ISSUE

PBM

SB

24.05.23

Rev

Description

Engineer

Checked

Date

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.

2. WORK TO FIGURED DIMENSIONS ONLY.

3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.

Drawing:

Small MonoBloc EDLA 04-08 (1 PHASE)

THIRD PARTY CYLINDER,

DHW & UFH

Drawing Status:

PRELIMINARY

Telephone: 01932 879 070 (Option 1)

Email: heating@daikin.co.uk

DAIKIN

altherma

1

2

3

4

5


6

7


8

35

ST 165: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW, Radiators and UFH - **Mechanical**




ST 165: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW, Radiators and UFH - **Electrical**




ST 165: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW, Radiators and UFH - Key Data

1		2		3		4		5		6		7		8																																																																																																																							
Drawing Number: ST-165 (3 of 3)		Scale: NTS@ A3		Revision: P3		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																																																													
FIRST FIX						INSTALLATION PHASE						PRE-COMMISSIONING																																																																																																																									
<table><tr><th colspan="4">TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA04EV3</th><th>EDLA06EV3</th><th>EDLA08EV3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td colspan="3">MINIMUM 28</td></tr><tr><td>FLOW RATE (l/min) CENTRAL HEATING</td><td>13.2</td><td>17.2</td><td>22.4</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td colspan="3">SEE TABLE 3</td></tr><tr><td>MAX CURRENT (A)</td><td colspan="2">19.9</td><td>24</td></tr><tr><td>FUSE (A)</td><td colspan="2">20</td><td>25</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td colspan="3">230v</td></tr><tr><td>MAX CURRENT (A) DHW BSH</td><td colspan="3">13.04</td></tr><tr><td>FUSE (A)</td><td colspan="3">16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td colspan="3">1.5</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td colspan="3">10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td colspan="3">5</td></tr><tr><td>HEIGHT (mm)</td><td colspan="3">770</td></tr><tr><td>WIDTH (mm)</td><td colspan="3">1250</td></tr><tr><td>DEPTH (mm)</td><td colspan="3">362</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td colspan="3">88</td></tr><tr><td>WEIGHT FULL (kg)</td><td colspan="3">96</td></tr></table>						TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE				EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3	PRIMARY PIPEWORK (mm)	MINIMUM 28			FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4	MINIMUM WATER VOLUME (Litres)	SEE TABLE 3			MAX CURRENT (A)	19.9		24	FUSE (A)	20		25	MAINS FOR DHW BSH (K3M)	230v			MAX CURRENT (A) DHW BSH	13.04			FUSE (A)	16			MINIMUM CABLE (mm²) FOR MMI	1.5			MAXIMUM DISTANCE TO TANK (m)	10			MAXIMUM LEVEL DIFFERENCE (m)	5			HEIGHT (mm)	770			WIDTH (mm)	1250			DEPTH (mm)	362			WEIGHT EMPTY (kg)	88			WEIGHT FULL (kg)	96			<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>						TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	CHECKLIST BEFORE COMMISSIONING AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>							YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE																																																																																																																																					
EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3																																																																																																																																		
PRIMARY PIPEWORK (mm)	MINIMUM 28																																																																																																																																				
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4																																																																																																																																		
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3																																																																																																																																				
MAX CURRENT (A)	19.9		24																																																																																																																																		
FUSE (A)	20		25																																																																																																																																		
MAINS FOR DHW BSH (K3M)	230v																																																																																																																																				
MAX CURRENT (A) DHW BSH	13.04																																																																																																																																				
FUSE (A)	16																																																																																																																																				
MINIMUM CABLE (mm²) FOR MMI	1.5																																																																																																																																				
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																																																				
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																																																				
HEIGHT (mm)	770																																																																																																																																				
WIDTH (mm)	1250																																																																																																																																				
DEPTH (mm)	362																																																																																																																																				
WEIGHT EMPTY (kg)	88																																																																																																																																				
WEIGHT FULL (kg)	96																																																																																																																																				
TABLE 2 - INSULATION THICKNESS																																																																																																																																					
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																																																				
<20	19																																																																																																																																				
20-30	32																																																																																																																																				
30-40	40																																																																																																																																				
40-50	50																																																																																																																																				
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																																																				
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																																																				
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																																																				
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																																																				
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																																																				
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																																																				
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																																																				
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																																																				
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																																																				
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																																																				
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																																																				
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																																																				
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																																																				
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																																																				
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																																				
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																																																				
<table><tr><th colspan="4">TABLE 3 - MINIMUM WATER VOLUME</th></tr><tr><th colspan="2">IF</th><th colspan="2">THEN THE MINIMUM WATER VOLUME IS...</th></tr><tr><td colspan="4">HEATING/DEFROST OPERATION AND...</td></tr><tr><td></td><td>PREHEATING ON THE TANK IS POSSIBLE</td><td colspan="2">0ltrs</td></tr><tr><td></td><td>PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT</td><td colspan="2">10ltrs</td></tr><tr><td></td><td>PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND....</td><td colspan="2"></td></tr><tr><td></td><td>THE RETURN FLOW TEMPERATURE IS >15°C</td><td colspan="2">20ltrs</td></tr><tr><td></td><td>THE RETURN FLOW TEMPERATURE IS ,15°C</td><td colspan="2">50ltrs</td></tr></table>						TABLE 3 - MINIMUM WATER VOLUME				IF		THEN THE MINIMUM WATER VOLUME IS...		HEATING/DEFROST OPERATION AND...					PREHEATING ON THE TANK IS POSSIBLE	0ltrs			PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs			PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND....				THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs			THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs		THIRD PARTY TANK TECHNICAL REQUIREMENTS The specifier must take care to ensure that the cylinder is suitable for the heat pump application. Where a third party cylinder has been specified, Daikin strongly recommend that the specifier/installer checks the following points: • Cylinder has a dry pocket to accommodate the Daikin cylinder sensor (Diameter 8mm, minimum recommend depth 28mm). • The heat exchanger coil is suitably dimensioned for the heat input from the relevant heat pump. • The immersion heater is positioned above the indirect heating coil. • Insulation of tank and the standing heat loss meets the requirements of the current building regulations. • Cylinder has the following approvals: G3, Water Regulations, Building Regulations, CE marked.																																																																																															
TABLE 3 - MINIMUM WATER VOLUME																																																																																																																																					
IF		THEN THE MINIMUM WATER VOLUME IS...																																																																																																																																			
HEATING/DEFROST OPERATION AND...																																																																																																																																					
	PREHEATING ON THE TANK IS POSSIBLE	0ltrs																																																																																																																																			
	PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs																																																																																																																																			
	PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND....																																																																																																																																				
	THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs																																																																																																																																			
	THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs																																																																																																																																			
 DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC  UNBOXING SMALL MONOBLOC  MMI USER GUIDE  3-WAY VALVE EXPLAINED  SMALL MONOBLOC PRODUCT VIDEO						CHECKLIST DURING COMMISSIONING <table><tr><td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>TO PERFORM AN AIR PURGE.</td></tr><tr><td></td><td>TO PERFORM A TEST RUN.</td></tr><tr><td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr><tr><td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr></table>							THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																																
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																																				
	TO PERFORM AN AIR PURGE.																																																																																																																																				
	TO PERFORM A TEST RUN.																																																																																																																																				
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																																																																				
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																																																				
NOTES • AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. • IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT. • ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. • ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. • EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. • FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																																																																					
<table><tr><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>P3</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>25.09.24</td><td rowspan="4">1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.</td></tr><tr><td>P2</td><td>MIXING VALVE UPDATED</td><td>PBM</td><td>SB</td><td>27.03.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>												P3	PHASE 2 UPDATES	PBM	SB	25.09.24	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.	P2	MIXING VALVE UPDATED	PBM	SB	27.03.24	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	Drawing: Small MonoBloc EDLA (1 PHASE) THIRD PARTY CYLINDER, THIRD PARTY CONTROLS, DHW, RADIATORS & UFH		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																																																
P3	PHASE 2 UPDATES	PBM	SB	25.09.24	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.																																																																																																																																
P2	MIXING VALVE UPDATED	PBM	SB	27.03.24																																																																																																																																	
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																																																																																																	
Rev	Description	Engineer	Checked	Date																																																																																																																																	

ST 167: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW & 2 Zone Radiator Circuit - **Mechanical**




ST 167: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW & 2 Zone Radiator Circuit - **Electrical**




ST 167: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW & 2 Zone Radiator Circuit - Key Data

1		2		3		4		5		6		7		8																																																																																																																					
Drawing Number: ST-167 (3 of 3)		Scale: NTS@ A3		Revision: P1		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																																																											
FIRST FIX				INSTALLATION PHASE				PRE-COMMISSIONING																																																																																																																											
<table><tr><th colspan="4">TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA04EV3</th><th>EDLA06EV3</th><th>EDLA08EV3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td colspan="3">MINIMUM 28</td></tr><tr><td>FLOW RATE (l/min) CENTRAL HEATING</td><td>13.2</td><td>17.2</td><td>22.4</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td colspan="3">SEE TABLE 3</td></tr><tr><td>MAX CURRENT (A)</td><td colspan="2">19.9</td><td>24</td></tr><tr><td>FUSE (A)</td><td colspan="2">20</td><td>25</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td colspan="3">230v</td></tr><tr><td>MAX CURRENT (A) DHW BSH</td><td colspan="3">13.04</td></tr><tr><td>FUSE (A)</td><td colspan="3">16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td colspan="3">1.5</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td colspan="3">10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td colspan="3">5</td></tr><tr><td>HEIGHT (mm)</td><td colspan="3">770</td></tr><tr><td>WIDTH (mm)</td><td colspan="3">1250</td></tr><tr><td>DEPTH (mm)</td><td colspan="3">362</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td colspan="3">88</td></tr><tr><td>WEIGHT FULL (kg)</td><td colspan="3">96</td></tr></table>				TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE				EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3	PRIMARY PIPEWORK (mm)	MINIMUM 28			FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4	MINIMUM WATER VOLUME (Litres)	SEE TABLE 3			MAX CURRENT (A)	19.9		24	FUSE (A)	20		25	MAINS FOR DHW BSH (K3M)	230v			MAX CURRENT (A) DHW BSH	13.04			FUSE (A)	16			MINIMUM CABLE (mm²) FOR MMI	1.5			MAXIMUM DISTANCE TO TANK (m)	10			MAXIMUM LEVEL DIFFERENCE (m)	5			HEIGHT (mm)	770			WIDTH (mm)	1250			DEPTH (mm)	362			WEIGHT EMPTY (kg)	88			WEIGHT FULL (kg)	96			<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>				TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	CHECKLIST BEFORE COMMISSIONING AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>((IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>									YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		((IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE																																																																																																																																			
EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3																																																																																																																																
PRIMARY PIPEWORK (mm)	MINIMUM 28																																																																																																																																		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4																																																																																																																																
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3																																																																																																																																		
MAX CURRENT (A)	19.9		24																																																																																																																																
FUSE (A)	20		25																																																																																																																																
MAINS FOR DHW BSH (K3M)	230v																																																																																																																																		
MAX CURRENT (A) DHW BSH	13.04																																																																																																																																		
FUSE (A)	16																																																																																																																																		
MINIMUM CABLE (mm²) FOR MMI	1.5																																																																																																																																		
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																																																		
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																																																		
HEIGHT (mm)	770																																																																																																																																		
WIDTH (mm)	1250																																																																																																																																		
DEPTH (mm)	362																																																																																																																																		
WEIGHT EMPTY (kg)	88																																																																																																																																		
WEIGHT FULL (kg)	96																																																																																																																																		
TABLE 2 - INSULATION THICKNESS																																																																																																																																			
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																																																		
<20	19																																																																																																																																		
20-30	32																																																																																																																																		
30-40	40																																																																																																																																		
40-50	50																																																																																																																																		
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																																																		
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																																																		
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																																																		
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																																																		
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																																																		
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																																																		
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																																																		
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																																																		
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																																																		
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																																																		
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																																																		
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																																																		
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																																																		
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																																																		
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																																		
	((IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																																																		
<table><tr><th colspan="3">TABLE 3 - MINIMUM WATER VOLUME</th></tr><tr><th>IF</th><th colspan="2">THEN THE MINIMUM WATER VOLUME IS...</th></tr><tr><td colspan="3">HEATING/DEFROST OPERATION AND...</td></tr><tr><td rowspan="3"> PREHEATING ON THE TANK IS POSSIBLE PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND... </td><td colspan="2">0ltrs</td></tr><tr><td colspan="2">10ltrs</td></tr><tr><td colspan="2"></td></tr><tr><td rowspan="2"> THE RETURN FLOW TEMPERATURE IS >15°C THE RETURN FLOW TEMPERATURE IS .15°C </td><td colspan="2">20ltrs</td></tr><tr><td colspan="2">50ltrs</td></tr></table>				TABLE 3 - MINIMUM WATER VOLUME			IF	THEN THE MINIMUM WATER VOLUME IS...		HEATING/DEFROST OPERATION AND...			PREHEATING ON THE TANK IS POSSIBLE PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...	0ltrs		10ltrs				THE RETURN FLOW TEMPERATURE IS >15°C THE RETURN FLOW TEMPERATURE IS .15°C	20ltrs		50ltrs		 DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC  UNBOXING SMALL MONOBLOC  MMI USER GUIDE  3-WAY VALVE EXPLAINED  SMALL MONOBLOC PRODUCT VIDEO				CHECKLIST DURING COMMISSIONING <table><tr><td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>TO PERFORM AN AIR PURGE.</td></tr><tr><td></td><td>TO PERFORM A TEST RUN.</td></tr><tr><td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr><tr><td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr></table>									THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																					
TABLE 3 - MINIMUM WATER VOLUME																																																																																																																																			
IF	THEN THE MINIMUM WATER VOLUME IS...																																																																																																																																		
HEATING/DEFROST OPERATION AND...																																																																																																																																			
PREHEATING ON THE TANK IS POSSIBLE PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...	0ltrs																																																																																																																																		
	10ltrs																																																																																																																																		
THE RETURN FLOW TEMPERATURE IS >15°C THE RETURN FLOW TEMPERATURE IS .15°C	20ltrs																																																																																																																																		
	50ltrs																																																																																																																																		
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																																		
	TO PERFORM AN AIR PURGE.																																																																																																																																		
	TO PERFORM A TEST RUN.																																																																																																																																		
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																																																																		
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																																																		
NOTES • AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. • IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT. • ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. • ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. • EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. • FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																																																																			
<table><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>PBM</td><td>SB</td><td>25.09.2024</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>				P1	PRELIMINARY ISSUE	PBM	SB	25.09.2024	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: Small MonoBloc EDLA 04-8 (1 PHASE) THIRD PARTY CYLINDER, THIRD PARTY CONTROLS, DHW & 2 ZONE RADIATOR CIRCUITS		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																																																															
P1	PRELIMINARY ISSUE	PBM	SB	25.09.2024																																																																																																																															
Rev	Description	Engineer	Checked	Date																																																																																																																															

ST 169: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW & 2 Zone Radiator Circuit - **Mechanical**




ST 169: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW & 2 Zone Radiator Circuit - **Electrical**




ST 169: EDLA Low Capacity Monobloc - Third Party Cylinder, Third Party Controls, DHW & 2 Zone Radiator Circuit - Key Data

1		2		3		4		5		6		7		8																																																																																																																	
Drawing Number: ST-169 (3 of 3)		Scale: NTS@ A3		Revision: P1		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPTD RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																																																							
FIRST FIX				INSTALLATION PHASE				PRE-COMMISSIONING																																																																																																																							
<table><tr><th colspan="4">TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA04EV3</th><th>EDLA06EV3</th><th>EDLA08EV3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td colspan="3">MINIMUM 28</td></tr><tr><td>FLOW RATE (l/min) CENTRAL HEATING</td><td>13.2</td><td>17.2</td><td>22.4</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td colspan="3">SEE TABLE 3</td></tr><tr><td>MAX CURRENT (A)</td><td colspan="2">19.9</td><td>24</td></tr><tr><td>FUSE (A)</td><td colspan="2">20</td><td>25</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td colspan="3">230v</td></tr><tr><td>MAX CURRENT (A) DHW BSH</td><td colspan="3">13.04</td></tr><tr><td>FUSE (A)</td><td colspan="3">16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td colspan="3">1.5</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td colspan="3">10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td colspan="3">5</td></tr><tr><td>HEIGHT (mm)</td><td colspan="3">770</td></tr><tr><td>WIDTH (mm)</td><td colspan="3">1250</td></tr><tr><td>DEPTH (mm)</td><td colspan="3">362</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td colspan="3">88</td></tr><tr><td>WEIGHT FULL (kg)</td><td colspan="3">96</td></tr></table>				TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE				EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3	PRIMARY PIPEWORK (mm)	MINIMUM 28			FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4	MINIMUM WATER VOLUME (Litres)	SEE TABLE 3			MAX CURRENT (A)	19.9		24	FUSE (A)	20		25	MAINS FOR DHW BSH (K3M)	230v			MAX CURRENT (A) DHW BSH	13.04			FUSE (A)	16			MINIMUM CABLE (mm²) FOR MMI	1.5			MAXIMUM DISTANCE TO TANK (m)	10			MAXIMUM LEVEL DIFFERENCE (m)	5			HEIGHT (mm)	770			WIDTH (mm)	1250			DEPTH (mm)	362			WEIGHT EMPTY (kg)	88			WEIGHT FULL (kg)	96			<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>				TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	CHECKLIST BEFORE COMMISSIONING AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>					YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE																																																																																																																															
EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3																																																																																																																												
PRIMARY PIPEWORK (mm)	MINIMUM 28																																																																																																																														
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4																																																																																																																												
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3																																																																																																																														
MAX CURRENT (A)	19.9		24																																																																																																																												
FUSE (A)	20		25																																																																																																																												
MAINS FOR DHW BSH (K3M)	230v																																																																																																																														
MAX CURRENT (A) DHW BSH	13.04																																																																																																																														
FUSE (A)	16																																																																																																																														
MINIMUM CABLE (mm²) FOR MMI	1.5																																																																																																																														
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																																														
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																																														
HEIGHT (mm)	770																																																																																																																														
WIDTH (mm)	1250																																																																																																																														
DEPTH (mm)	362																																																																																																																														
WEIGHT EMPTY (kg)	88																																																																																																																														
WEIGHT FULL (kg)	96																																																																																																																														
TABLE 2 - INSULATION THICKNESS																																																																																																																															
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																																														
<20	19																																																																																																																														
20-30	32																																																																																																																														
30-40	40																																																																																																																														
40-50	50																																																																																																																														
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																																														
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																																														
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																																														
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																																														
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																																														
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																																														
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																																														
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																																														
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																																														
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																																														
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																																														
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																																														
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																																														
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																																														
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																														
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																																														
<table><tr><th colspan="2">TABLE 3 - MINIMUM WATER VOLUME</th></tr><tr><th>IF</th><th>THEN THE MINIMUM WATER VOLUME IS...</th></tr><tr><td colspan="2">HEATING/DEFROST OPERATION AND...</td></tr><tr><td>PREHEATING ON THE TANK IS POSSIBLE</td><td>0ltrs</td></tr><tr><td>PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT</td><td>10ltrs</td></tr><tr><td>PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...</td><td></td></tr><tr><td>THE RETURN FLOW TEMPERATURE IS >15°C</td><td>20ltrs</td></tr><tr><td>THE RETURN FLOW TEMPERATURE IS ≤15°C</td><td>50ltrs</td></tr></table>				TABLE 3 - MINIMUM WATER VOLUME		IF	THEN THE MINIMUM WATER VOLUME IS...	HEATING/DEFROST OPERATION AND...		PREHEATING ON THE TANK IS POSSIBLE	0ltrs	PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs	PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...		THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs	THE RETURN FLOW TEMPERATURE IS ≤15°C	50ltrs	OVERVIEW OF PRE-PLUMBED CYLINDER WIRING CONNECTIONS <table><tr><td>CABLE SECTION 2.5mm²</td></tr><tr><td>MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M</td></tr><tr><td>CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.</td></tr><tr><td>CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA</td></tr><tr><td>MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M</td></tr><tr><td>THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK</td></tr></table>  DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC  UNBOXING SMALL MONOBLOC  MMI USER GUIDE  3-WAY VALVE EXPLAINED  SMALL MONOBLOC PRODUCT VIDEO				CABLE SECTION 2.5mm²	MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M	CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.	CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA	MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M	THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK																																																																																																		
TABLE 3 - MINIMUM WATER VOLUME																																																																																																																															
IF	THEN THE MINIMUM WATER VOLUME IS...																																																																																																																														
HEATING/DEFROST OPERATION AND...																																																																																																																															
PREHEATING ON THE TANK IS POSSIBLE	0ltrs																																																																																																																														
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs																																																																																																																														
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...																																																																																																																															
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs																																																																																																																														
THE RETURN FLOW TEMPERATURE IS ≤15°C	50ltrs																																																																																																																														
CABLE SECTION 2.5mm²																																																																																																																															
MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M																																																																																																																															
CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.																																																																																																																															
CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA																																																																																																																															
MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M																																																																																																																															
THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK																																																																																																																															
NOTES • AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. • IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT. • ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. • ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. • EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. • FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)				CHECKLIST DURING COMMISSIONING <table><tr><td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>TO PERFORM AN AIR PURGE.</td></tr><tr><td></td><td>TO PERFORM A TEST RUN.</td></tr><tr><td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr><tr><td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr></table>					THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																														
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																																														
	TO PERFORM AN AIR PURGE.																																																																																																																														
	TO PERFORM A TEST RUN.																																																																																																																														
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																																																														
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																																														
1 <table><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>PBM</td><td>SB</td><td>25.09.24</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>				P1	PRELIMINARY ISSUE	PBM	SB	25.09.24	Rev	Description	Engineer	Checked	Date	2 1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.				3 Drawing: Small MonoBloc Class 4-8 EDLA (1 PHASE) PRE PLUMBED CYLINDER, THIRD PARTY CONTROLS, DHW & 2 ZONE RADIATORS				4 Drawing Status: PRELIMINARY				5 Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk				6 																																																																																																	
P1	PRELIMINARY ISSUE	PBM	SB	25.09.24																																																																																																																											
Rev	Description	Engineer	Checked	Date																																																																																																																											

ST 171: EDLA Low Capacity Monobloc - Preplumbed Cylinder, DHW Radiators - Mechanical



ST 171: EDLA Low Capacity Monobloc - Preplumbed Cylinder, DHW Radiators- **Electrical**



ST 171: EDLA Low Capacity Monobloc - Preplumbed Cylinder, DHW Radiators- Key Data

1

Drawing Number:
ST-171 (3 of 3)

2

Scale:
NTS@ A3

3

Revision:
P3

4

• SEE PAGE 1 FOR MECHANICAL SET UP.
• SEE PAGE 2 FOR DETAILED WIRING.
• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

5

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING
• OPTIONAL FOR HEAT METERS
• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

6

7

8

FIRST FIX

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9	24	
FUSE (A)	20	25	
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

IF	THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...	
PREHEATING ON THE TANK IS POSSIBLE	0ltrs
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...	
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs
THE RETURN FLOW TEMPERATURE IS ≤15°C	50ltrs

INSTALLATION PHASE

PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)
<20	19
20-30	32
30-40	40
40-50	50

OVERVIEW OF PRE-PLUMBED CYLINDER WIRING CONNECTIONS

CABLE SECTION 2.5mm²
MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M
CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.
CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA
MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M
THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK

PRE-COMMISSIONING

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	((IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.

• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.

• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.

• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.

• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.

• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.

2. WORK TO FIGURED DIMENSIONS ONLY.

3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.

P3

PHASE 2 UPDATES

PBM

SB

25.09.24

P2

FLOW SWITCH REFERENCE UPDATE

PBM

SB

07.06.24

P1

PRELIMINARY ISSUE

PBM

SB

30.05.23

Rev

Description

Engineer

Checked

Date

Drawing:

Small MonoBloc EDLA 04-08 (1 PHASE)

PRE PLUMBED CYLINDER, DOMESTIC HOT WATER

& RADIATORS

Drawing Status:

PRELIMINARY

Telephone: 01932 879 070 (Option 1)


Email: heating@daikin.co.uk

DAIKIN


altherma

47

ST 172: EDLA Low Capacity Monobloc - Preplumbed Cylinder, DHW & UFH - **Mechanical**




ST 172: EDLA Low Capacity Monobloc - Preplumbed Cylinder, DHW & UFH - **Electrical**




ST 172: EDLA Low Capacity Monobloc - Preplumbed Cylinder, DHW & UFH - Key Data

1		2		3		4		5		6		7		8					
Drawing Number: ST-172 (3 of 3)		Scale: NTS@ A3		Revision: P3		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.											
FIRST FIX						INSTALLATION PHASE						PRE-COMMISSIONING							
TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE						TABLE 2 - INSULATION THICKNESS						CHECKLIST BEFORE COMMISSIONING							
EQUIPMENT				EDLA04EV3		EDLA06EV3		EDLA08EV3		PIPING LENGTH (m)		MINIMUM INSULATION THICKNESS (mm)				AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.			
PRIMARY PIPEWORK (mm)				13.2		17.2		22.4		<20		19				YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.			
FLOW RATE (l/min) CENTRAL HEATING				20		25				20-30		32				THE OUTDOOR UNIT IS PROPERLY MOUNTED.			
MINIMUM WATER VOLUME (Litres)				19.9		24				30-40		40				FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.			
MAX CURRENT (A)				230v						40-50		50				THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.			
FUSE (A)				13.04												THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.			
MAINS FOR DHW BSH (K3M)				16												THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.			
MAX CURRENT (A) DHW BSH				1.5												THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.			
FUSE (A)				10												ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.			
MINIMUM CABLE (mm²) FOR MMI				5												ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.			
MAXIMUM DISTANCE TO TANK (m)				770												THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.			
MAXIMUM LEVEL DIFFERENCE (m)				1250												THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.			
HEIGHT (mm)				362												THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.			
WIDTH (mm)				88												FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.			
DEPTH (mm)				96												THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.			
WEIGHT EMPTY (kg)																THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.			
WEIGHT FULL (kg)																(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.			
TABLE 3 - MINIMUM WATER VOLUME						OVERVIEW OF PRE-PLUMBED CYLINDER WIRING CONNECTIONS						CHECKLIST DURING COMMISSIONING							
IF			THEN THE MINIMUM WATER VOLUME IS...			CABLE SECTION 2.5mm²						THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.							
HEATING/DEFROST OPERATION AND...						MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M						TO PERFORM AN AIR PURGE.							
PREHEATING ON THE TANK IS POSSIBLE		0ltrs				CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.						TO PERFORM A TEST RUN.							
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT		10ltrs				CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA						TO PERFORM AN ACTUATOR TEST RUN.							
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...						MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M						UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.							
THE RETURN FLOW TEMPERATURE IS >15°C		20ltrs				THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK													
THE RETURN FLOW TEMPERATURE IS ,15°C		50ltrs																	
NOTES						DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC													
• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.						UNBOXING SMALL MONOBLOC						3-WAY VALVE EXPLAINED							
• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.						MMI USER GUIDE						SMALL MONOBLOC PRODUCT VIDEO							
• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.																			
• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.																			
• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.																			
• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																			
1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.						Drawing: Small MonoBloc EDLA 04-08 (1 PHASE)						Drawing Status: PRELIMINARY							
2. WORK TO FIGURED DIMENSIONS ONLY.						PRE PLUMBED CYLINDER, DOMESTIC HOT WATER						Telephone: 01932 879 070 (Option 1)							
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.						& UNDERFLOOR HEATING						Email: heating@daikin.co.uk							
Rev Description Engineer Checked Date																			

ST 173: EDLA Low Capacity Monobloc - Preplumbed Cylinder Third Party Controls DHW Radiators UFH - **Mechanical**



ST 173: EDLA Low Capacity Monobloc - Preplumbed Cylinder Third Party Controls DHW Radiators UFH - **Electrical**



ST 173: EDLA Low Capacity Monobloc - Preplumbed Cylinder Third Party Controls DHW Radiators UFH - Key Data

1

2

3

4

5

6

7

8

Drawing Number:
ST-173 (3 of 3)

Scale:
NTS@ A3

Revision:
P5

• SEE PAGE 1 FOR MECHANICAL SET UP.
• SEE PAGE 2 FOR DETAILED WIRING.
• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

• DPT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING
• OPTIONAL FOR HEAT METERS
• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.

FIRST FIX

INSTALLATION PHASE

PRE-COMMISSIONING

TABLE 1 - DATA - MONOBLOC HEATING ONLY 1 PHASE

EQUIPMENT	EDLA04EV3	EDLA06EV3	EDLA08EV3
PRIMARY PIPEWORK (mm)	MINIMUM 28		
FLOW RATE (l/min) CENTRAL HEATING	13.2	17.2	22.4
MINIMUM WATER VOLUME (Litres)	SEE TABLE 3		
MAX CURRENT (A)	19.9	24	
FUSE (A)	20	25	
MAINS FOR DHW BSH (K3M)	230v		
MAX CURRENT (A) DHW BSH	13.04		
FUSE (A)	16		
MINIMUM CABLE (mm²) FOR MMI	1.5		
MAXIMUM DISTANCE TO TANK (m)	10		
MAXIMUM LEVEL DIFFERENCE (m)	5		
HEIGHT (mm)	770		
WIDTH (mm)	1250		
DEPTH (mm)	362		
WEIGHT EMPTY (kg)	88		
WEIGHT FULL (kg)	96		

TABLE 2 - INSULATION THICKNESS

PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)
<20	19
20-30	32
30-40	40
40-50	50

TABLE 3 - MINIMUM WATER VOLUME

IF	THEN THE MINIMUM WATER VOLUME IS...
HEATING/DEFROST OPERATION AND...	
PREHEATING ON THE TANK IS POSSIBLE	0ltrs
PREHEATING ON THE TANK IS NOT POSSIBLE, BUT A BACK UP HEATER (INTERNAL OR EXTERNAL) IS PRESENT	10ltrs
PREHEATING THE TANK IS NOT POSSIBLE, THERE IS NO BACK UP HEATER, AND...	
THE RETURN FLOW TEMPERATURE IS >15°C	20ltrs
THE RETURN FLOW TEMPERATURE IS ,15°C	50ltrs

OVERVIEW OF PRE-PLUMBED CYLINDER WIRING CONNECTIONS

CABLE SECTION 2.5mm²

MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M

CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.

CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA

MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M

THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK

DAIKIN ALTHERMA LOW TEMPERATURE MONOBLOC

UNBOXING SMALL MONOBLOC

MMI USER GUIDE

3-WAY VALVE EXPLAINED

SMALL MONOBLOC PRODUCT VIDEO

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.

NOTES

• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.

• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW2) MUST BE PURCHASE AND INSTALLED IN THE UNIT.

• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.

• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.

• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.

• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)

P5 PHASE 2 UPDATES

P4 FLOW SWITCH REFERENCE UPDATE

P3 MIXING VALVE UPDATED

P2 WIRING UPDATED

P1 PRELIMINARY ISSUE

Rev

PBM

PBM

PBM

PBM

PBM

Engineer

SB

SB

SB

SB

SB

Checked

25.09.24

07.06.24

26.03.24

20.10.23

30.05.23

Date

1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.

2. WORK TO FIGURED DIMENSIONS ONLY.

3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.

Drawing:

Small MonoBloc EDLA 04-08 (1 PHASE)

PRE PLUMBED CYLINDER, THIRD PARTY CONTROLS,

DHW, RADIATORS & UFH

Drawing Status:

PRELIMINARY

Telephone: 01932 879 070 (Option 1)

Email: heating@daikin.co.uk

DAIKIN

altherma

1

2

3

4

5


6

7


8

53

ST 202: EDLA High Capacity Monobloc - DHW Only - Mechanical




ST 202: EDLA High Capacity Monobloc - DHW Only - **Electrical**




ST 202: EDLA High Capacity Monobloc - DHW Only - Key Data

1	2	3	4	5	6	7	8																																																																
Drawing Number: ST-202 (3 of 3)		Scale: NTS@A3	Revision: P3	• SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																	
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING																																																																		
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		TABLE 2 - INSULATION THICKNESS			CHECKLIST BEFORE COMMISSIONING																																																																		
<table><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>			PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>			YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.	THE OUTDOOR UNIT IS PROPERLY MOUNTED.	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																						
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																																						
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																						
MIN FLOW RATE (l/min) DHW	28																																																																						
MINIMUM WATER VOLUME (Litres)	20																																																																						
MAX CURRENT (A)	30.8																																																																						
FUSE (A)	32																																																																						
MAINS FOR BUH (X9M)	230v																																																																						
FUSE (A)	16																																																																						
MAINS FOR DHW BSH (K3M)	230v																																																																						
FUSE (A)	16																																																																						
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																						
MAXIMUM DISTANCE TO TANK (m)	10																																																																						
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																						
HEIGHT (mm)	870																																																																						
WIDTH (mm)	1380																																																																						
DEPTH (mm)	460																																																																						
WEIGHT EMPTY (kg)	149																																																																						
WEIGHT FULL (kg)	157																																																																						
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																						
<20	19																																																																						
20-30	32																																																																						
30-40	40																																																																						
40-50	50																																																																						
YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																							
THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																							
FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																							
THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																							
THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																							
THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																							
THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																							
ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																							
ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																							
THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																							
THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																							
THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																							
FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																							
THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																							
THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																							
(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																							
NOTES																																																																							
• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.																																																																							
• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT.																																																																							
• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.																																																																							
• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.																																																																							
• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.																																																																							
• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																							
1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.		Drawing: MonoBloc		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																	
2. WORK TO FIGURED DIMENSIONS ONLY.		EDLA 09-16 (1 PHASE)				DAIKIN altherma																																																																	
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		DOMESTIC HOT WATER																																																																					
P2	PHASE 2 UPDATES	PBM	SB	06.09.24																																																																			
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																																			
Rev	Description	Engineer	Checked	Date																																																																			
1																																																																							
2																																																																							
3																																																																							
4																																																																							
5																																																																							
6																																																																							
7																																																																							
8																																																																							

ST 203: EDLA High Capacity Monobloc - Radiators Only - Mechanical




ST 203: EDLA High Capacity Monobloc - Radiators Only - Electrical




ST 203: EDLA High Capacity Monobloc - Radiators Only - Key Data

1	2	3	4	5	6	7	8																																																																																
Drawing Number: ST-203 (3 of 3)		Scale: NTS@ A3	Revision: P3	• SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																	
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING																																																																																		
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		TABLE 2 - INSULATION THICKNESS			CHECKLIST BEFORE COMMISSIONING																																																																																		
<table><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>			PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B: FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>				YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B: FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																																						
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																																																						
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																																						
MIN FLOW RATE (l/min) DHW	28																																																																																						
MINIMUM WATER VOLUME (Litres)	20																																																																																						
MAX CURRENT (A)	30.8																																																																																						
FUSE (A)	32																																																																																						
MAINS FOR BUH (X9M)	230v																																																																																						
FUSE (A)	16																																																																																						
MAINS FOR DHW BSH (K3M)	230v																																																																																						
FUSE (A)	16																																																																																						
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																																						
MAXIMUM DISTANCE TO TANK (m)	10																																																																																						
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																						
HEIGHT (mm)	870																																																																																						
WIDTH (mm)	1380																																																																																						
DEPTH (mm)	460																																																																																						
WEIGHT EMPTY (kg)	149																																																																																						
WEIGHT FULL (kg)	157																																																																																						
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																						
<20	19																																																																																						
20-30	32																																																																																						
30-40	40																																																																																						
40-50	50																																																																																						
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																						
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																						
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																						
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																						
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																						
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																						
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																						
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B: FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																						
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																						
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																						
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																						
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																						
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																						
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																						
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																						
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																						
		 UNBOXING LARGE MONOBLOC			 3-WAY VALVE EXPLAINED																																																																																		
		 MMI USER GUIDE			 DAIKIN ALTHERMA LARGE MONOBLOC																																																																																		
NOTES - AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. - IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. - ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. - ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. - EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. - FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																							
1		2		3		4																																																																																	
F		F		F		F																																																																																	
<table><tr><td>P3</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>07.09.24</td></tr><tr><td>P2</td><td>TABLE UPDATE</td><td>PBM</td><td>SB</td><td>28.07.23</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>		P3	PHASE 2 UPDATES	PBM	SB	07.09.24	P2	TABLE UPDATE	PBM	SB	28.07.23	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE) RADIATORS		Drawing Status: PRELIMINARY																																																													
P3	PHASE 2 UPDATES	PBM	SB	07.09.24																																																																																			
P2	TABLE UPDATE	PBM	SB	28.07.23																																																																																			
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																																																			
Rev	Description	Engineer	Checked	Date																																																																																			
						Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																																	
1		2		3		4																																																																																	
1		2		3		4																																																																																	

ST 204: EDLA High Capacity Monobloc - UFH Only - Mechanical



ST 204: EDLA High Capacity Monobloc - UFH Only - **Electrical**



ST 204: EDLA High Capacity Monobloc - UFH Only - Key Data

1

Drawing Number:
ST-204 (3 of 3)

2

Scale:
NTS@ A3

3

Revision:
P5

4

• SEE PAGE 1 FOR MECHANICAL SET UP.

• SEE PAGE 2 FOR DETAILED WIRING.

• SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.

5

• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING

• OPTIONAL FOR HEAT METERS

• ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.


6

7


8

<


ST 205: EDLA High Capacity Monobloc - DHW & Radiators - Mechanical




ST 205: EDLA High Capacity Monobloc - DHW & Radiators - **Electrical**



ST 206: EDLA High Capacity Monobloc - Third Party Controls DHW & UFH - **Mechanical**



ST 206: EDLA High Capacity Monobloc - Third Party Controls DHW & UFH - **Electrical**




ST 206: EDLA High Capacity Monobloc - Third Party Controls DHW & UFH - Key Data

1	2	3	4	5	6	7	8						
Drawing Number: ST-206 (3 of 3)	Scale: NTS@ A3	Revision: P5	 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.	• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.									
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING								
A													
B													
C													
D													
E													
F													

EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3
PRIMARY PIPEWORK (mm)	minimum 28mm
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22
MIN FLOW RATE (l/min) DHW	28
MINIMUM WATER VOLUME (Litres)	20
MAX CURRENT (A)	30.8
FUSE (A)	32
MAINS FOR BUH (X9M)	230v
FUSE (A)	16
MAINS FOR DHW BSH (K3M)	230v
FUSE (A)	16
MINIMUM CABLE (mm²) FOR MMI	0.75
MAXIMUM DISTANCE TO TANK (m)	10
MAXIMUM LEVEL DIFFERENCE (m)	5
HEIGHT (mm)	870
WIDTH (mm)	1380
DEPTH (mm)	460
WEIGHT EMPTY (kg)	149
WEIGHT FULL (kg)	157

No top-side obstacle
Suction-side obstacle





UNBOXING LARGE MONOBLOC



3-WAY VALVE EXPLAINED



MMI USER GUIDE



DAIKIN ALTHERMA LARGE MONOBLOC

CHECKLIST BEFORE COMMISSIONING

AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.

	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.

CHECKLIST DURING COMMISSIONING

	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.
	TO PERFORM AN AIR PURGE.
	TO PERFORM A TEST RUN.
	TO PERFORM AN ACTUATOR TEST RUN.
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.


NOTES

- AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.
- IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT.
- ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.
- ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.
- EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.
- FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)**


P5	PHASE 2 UPDATES	PBM	SB	04.09.24	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.	Drawing: MonoBloc EDLA 09-16 (1 PHASE) THIRD PARTY CONTROLS DHW & UFH	Drawing Status: PRELIMINARY	Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk	
P4	MIXING VALVE UPDATED	PBM	SB	27.03.24					
P3	WIRING CONNECTION UPDATED	PBM	SB	07.09.23					
P2	TABLE UPDATE	PBM	SB	28.07.23					
P1	PRELIMINARY ISSUE	RB	SB	16.05.23					
Rev	Description	Engineer	Checked	Date					

68

ST 213: EDLA High Capacity Monobloc - Third Party Controls DHW, Radiators & UFH - **Mechanical**




ST 213: EDLA High Capacity Monobloc - Third Party Controls DHW, Radiators & UFH - **Electrical**




ST 213: EDLA High Capacity Monobloc - Third Party Controls DHW, Radiators & UFH - Key Data

1	2	3	4	5	6	7	8																																																																																
Drawing Number: ST-213 (3 of 3)	Scale: NTS@ A3	Revision: P5	• SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																		
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING																																																																																		
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		TABLE 2 - INSULATION THICKNESS			CHECKLIST BEFORE COMMISSIONING																																																																																		
<table><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>minimum 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	minimum 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>			PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>				YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																																						
PRIMARY PIPEWORK (mm)	minimum 28mm																																																																																						
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																																						
MIN FLOW RATE (l/min) DHW	28																																																																																						
MINIMUM WATER VOLUME (Litres)	20																																																																																						
MAX CURRENT (A)	30.8																																																																																						
FUSE (A)	32																																																																																						
MAINS FOR BUH (X9M)	230v																																																																																						
FUSE (A)	16																																																																																						
MAINS FOR DHW BSH (K3M)	230v																																																																																						
FUSE (A)	16																																																																																						
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																																						
MAXIMUM DISTANCE TO TANK (m)	10																																																																																						
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																						
HEIGHT (mm)	870																																																																																						
WIDTH (mm)	1380																																																																																						
DEPTH (mm)	460																																																																																						
WEIGHT EMPTY (kg)	149																																																																																						
WEIGHT FULL (kg)	157																																																																																						
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																						
<20	19																																																																																						
20-30	32																																																																																						
30-40	40																																																																																						
40-50	50																																																																																						
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																						
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																						
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																						
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																						
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																						
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																						
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																						
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																						
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																						
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																						
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																						
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																						
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																						
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																						
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																						
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																						
		 UNBOXING LARGE MONOBLOC			 3-WAY VALVE EXPLAINED																																																																																		
		 MMI USER GUIDE			 DAIKIN ALTHERMA LARGE MONOBLOC																																																																																		
NOTES - AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. - IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. - ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. - ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. - EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																							
<table><tr><td>P5</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>29.08.24</td></tr><tr><td>P4</td><td>MIXING VALVE UPDATED</td><td>PBM</td><td>SB</td><td>27.03.24</td></tr><tr><td>P3</td><td>WIRING CONNECTION UPDATED</td><td>PBM</td><td>SB</td><td>07.09.23</td></tr><tr><td>P2</td><td>TABLE UPDATE</td><td>PBM</td><td>SB</td><td>28.07.23</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>		P5	PHASE 2 UPDATES	PBM	SB	29.08.24	P4	MIXING VALVE UPDATED	PBM	SB	27.03.24	P3	WIRING CONNECTION UPDATED	PBM	SB	07.09.23	P2	TABLE UPDATE	PBM	SB	28.07.23	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE) THIRD PARTY CONTROLS DHW, RADIATOR & UFH		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																	
P5	PHASE 2 UPDATES	PBM	SB	29.08.24																																																																																			
P4	MIXING VALVE UPDATED	PBM	SB	27.03.24																																																																																			
P3	WIRING CONNECTION UPDATED	PBM	SB	07.09.23																																																																																			
P2	TABLE UPDATE	PBM	SB	28.07.23																																																																																			
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																																																			
Rev	Description	Engineer	Checked	Date																																																																																			
1	2	3	4	5	6	7	8																																																																																

ST 215: EDLA High Capacity Monobloc - Third Party Controls Radiators & UFH - **Mechanical**




ST 215: EDLA High Capacity Monobloc - Third Party Controls Radiators & UFH - **Electrical**




ST 215: EDLA High Capacity Monobloc - Third Party Controls Radiators & UFH - Key Data

1	2	3	4	5	6	7	8																																																
Drawing Number: ST-215 (3 of 3)	Scale: NTS@ A3	Revision: P5	• SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																		
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING																																																		
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		TABLE 2 - INSULATION THICKNESS			CHECKLIST BEFORE COMMISSIONING																																																		
<table><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>minimum 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	minimum 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>			PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.		
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																						
PRIMARY PIPEWORK (mm)	minimum 28mm																																																						
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																						
MIN FLOW RATE (l/min) DHW	28																																																						
MINIMUM WATER VOLUME (Litres)	20																																																						
MAX CURRENT (A)	30.8																																																						
FUSE (A)	32																																																						
MAINS FOR BUH (X9M)	230v																																																						
FUSE (A)	16																																																						
MAINS FOR DHW BSH (K3M)	230v																																																						
FUSE (A)	16																																																						
MINIMUM CABLE (mm²) FOR MMI	0.75																																																						
MAXIMUM DISTANCE TO TANK (m)	10																																																						
MAXIMUM LEVEL DIFFERENCE (m)	5																																																						
HEIGHT (mm)	870																																																						
WIDTH (mm)	1380																																																						
DEPTH (mm)	460																																																						
WEIGHT EMPTY (kg)	149																																																						
WEIGHT FULL (kg)	157																																																						
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																						
<20	19																																																						
20-30	32																																																						
30-40	40																																																						
40-50	50																																																						
NOTES		CHECKLIST DURING COMMISSIONING																																																					
• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.		THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																					
• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT.		TO PERFORM AN AIR PURGE.																																																					
• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.		TO PERFORM A TEST RUN.																																																					
• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.		TO PERFORM AN ACTUATOR TEST RUN.																																																					
• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																					
• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																							
P5 PHASE 2 UPDATES PBM SB 06.09.24		1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE)		Drawing Status: PRELIMINARY																																																	
P4 MIXING VALVE UPDATED PBM SB 27.03.24		2. WORK TO FIGURED DIMENSIONS ONLY.		THIRD PARTY CONTROLS		Telephone: 01932 879 070 (Option 1)																																																	
P3 WIRING CONNECTION UPDATED PBM SB 07.09.23		3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		RADIATOR & UFH		Email: heating@daikin.co.uk																																																	
P2 TABLE UPDATE PBM SB 28.07.23																																																							
P1 PRELIMINARY ISSUE RB SB 16.05.23																																																							
Rev	Description	Engineer	Checked	Date																																																			
1																																																							


ST 217: EDLA High Capacity Monobloc - Third Party Cylinder DHW & 2 Zone Radiators - **Mechanical**




ST 217: EDLA High Capacity Monobloc - Third Party Cylinder DHW & 2 Zone Radiators - **Electrical**




ST 217: EDLA High Capacity Monobloc - Third Party Cylinder DHW & 2 Zone Radiators - Key Data

1		2		3		4		5		6		7		8																																																																																									
Drawing Number: ST-217 (3 of 3)				Scale: NTS@ A3		Revision: P2		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																													
FIRST FIX								INSTALLATION PHASE				PRE-COMMISSIONING																																																																																											
												CHECKLIST BEFORE COMMISSIONING																																																																																											
												AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.																																																																																											
<table><tr><th colspan="2">TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>								TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>								TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	<table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>					YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE																																																																																																							
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																																																						
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																																																																						
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																																																						
MIN FLOW RATE (l/min) DHW	28																																																																																																						
MINIMUM WATER VOLUME (Litres)	20																																																																																																						
MAX CURRENT (A)	30.8																																																																																																						
FUSE (A)	32																																																																																																						
MAINS FOR BUH (X9M)	230v																																																																																																						
FUSE (A)	16																																																																																																						
MAINS FOR DHW BSH (K3M)	230v																																																																																																						
FUSE (A)	16																																																																																																						
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																																																						
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																						
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																						
HEIGHT (mm)	870																																																																																																						
WIDTH (mm)	1380																																																																																																						
DEPTH (mm)	460																																																																																																						
WEIGHT EMPTY (kg)	149																																																																																																						
WEIGHT FULL (kg)	157																																																																																																						
TABLE 2 - INSULATION THICKNESS																																																																																																							
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																						
<20	19																																																																																																						
20-30	32																																																																																																						
30-40	40																																																																																																						
40-50	50																																																																																																						
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																						
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																						
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																						
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																						
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																						
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																						
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																						
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																						
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																						
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																						
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																						
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																						
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																						
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																						
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																						
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																						
								 UNBOXING LARGE MONOBLOC				 3-WAY VALVE EXPLAINED																																																																																											
								 MMI USER GUIDE				 DAIKIN ALTHERMA LARGE MONOBLOC																																																																																											
												CHECKLIST DURING COMMISSIONING																																																																																											
												<table><tr><td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>TO PERFORM AN AIR PURGE.</td></tr><tr><td></td><td>TO PERFORM A TEST RUN.</td></tr><tr><td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr><tr><td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr></table>					THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																														
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																						
	TO PERFORM AN AIR PURGE.																																																																																																						
	TO PERFORM A TEST RUN.																																																																																																						
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																																						
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																																						
NOTES																																																																																																							
• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN.																																																																																																							
• IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT.																																																																																																							
• ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT.																																																																																																							
• ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S.																																																																																																							
• EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA.																																																																																																							
• FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																																							
<table><tr><td></td><td></td><td></td><td></td><td></td></tr><tr><td>P2</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>28.08.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>										P2	PHASE 2 UPDATES	PBM	SB	28.08.24	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.					Drawing: MonoBloc EDLA 09-16 (1 PHASE) THIRD PARTY CONTROLS DHW& 2 ZONE RADIATOR CIRCUITS			Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																				
P2	PHASE 2 UPDATES	PBM	SB	28.08.24																																																																																																			
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																																																																			
Rev	Description	Engineer	Checked	Date																																																																																																			
1		2		3		4		5		6		7		8																																																																																									


ST 261: EDLA High Capacity Monobloc - Third Party Controls Cylinder & DHW - **Mechanical**




ST 261: EDLA High Capacity Monobloc - Third Party Controls Cylinder & DHW - **Electrical**




ST 261: EDLA High Capacity Monobloc - Third Party Controls Cylinder & DHW - Key Data

1		2		3		4		5		6		7		8																																																																																							
Drawing Number: ST-261 (3 of 3)				Scale: NTS@ A3		Revision: P2		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.				• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																									
FIRST FIX						INSTALLATION PHASE						PRE-COMMISSIONING																																																																																									
												<u>CHECKLIST BEFORE COMMISSIONING</u> AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.																																																																																									
<table><tr><th colspan="2">TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>						TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table> THIRD PARTY TANK TECHNICAL REQUIREMENTS The specifier must take care to ensure that the cylinder is suitable for the heat pump application. Where a third party cylinder has been specified, Daikin strongly recommend that the specifier/installer checks the following points: • Cylinder has a dry pocket to accommodate the Daikin cylinder sensor (Diameter 8mm, minimum recommend depth 28mm). • The heat exchanger coil is suitably dimensioned for the heat input from the relevant heat pump. • The immersion heater is positioned above the indirect heating coil. • Insulation of tank and the standing heat loss meets the requirements of the current building regulations. • Cylinder has the following approvals: G3, Water Regulations, Building Regulations, CE marked.						TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	<table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>							YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE																																																																																																					
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																																																				
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																																																																				
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																																																				
MIN FLOW RATE (l/min) DHW	28																																																																																																				
MINIMUM WATER VOLUME (Litres)	20																																																																																																				
MAX CURRENT (A)	30.8																																																																																																				
FUSE (A)	32																																																																																																				
MAINS FOR BUH (X9M)	230v																																																																																																				
FUSE (A)	16																																																																																																				
MAINS FOR DHW BSH (K3M)	230v																																																																																																				
FUSE (A)	16																																																																																																				
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																																																				
MAXIMUM DISTANCE TO TANK (m)	10																																																																																																				
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																																				
HEIGHT (mm)	870																																																																																																				
WIDTH (mm)	1380																																																																																																				
DEPTH (mm)	460																																																																																																				
WEIGHT EMPTY (kg)	149																																																																																																				
WEIGHT FULL (kg)	157																																																																																																				
TABLE 2 - INSULATION THICKNESS																																																																																																					
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																																				
<20	19																																																																																																				
20-30	32																																																																																																				
30-40	40																																																																																																				
40-50	50																																																																																																				
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																																				
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																																				
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																																				
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																																				
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																																				
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																																				
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																																				
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																																				
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																																				
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																																				
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																																				
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																																				
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																																				
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																																				
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																																				
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																																				
						UNBOXING LARGE MONOBLOC 3-WAY VALVE EXPLAINED MMI USER GUIDE DAIKIN ALTHERMA LARGE MONOBLOC																																																																																															
NOTES • AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. • IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. • ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. • ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. • EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. • FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																																					
<table><tr><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td></tr><tr><td>P2</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>07.09.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>																P2	PHASE 2 UPDATES	PBM	SB	07.09.24	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.				Drawing: MonoBloc EDLA 09-16 (1 PHASE) THIRD PARTY CYLINDER, DOMESTIC HOT WATER		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																														
P2	PHASE 2 UPDATES	PBM	SB	07.09.24																																																																																																	
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																																																																	
Rev	Description	Engineer	Checked	Date																																																																																																	
1		2		3		4		5		6		7		8																																																																																							


ST 262: EDLA High Capacity Monobloc - Third Party Cylinder DHW & Radiators - **Mechanical**




ST 262: EDLA High Capacity Monobloc - Third Party Cylinder DHW & Radiators - **Electrical**




ST 262: EDLA High Capacity Monobloc - Third Party Cylinder DHW & Radiators - Key Data

1	2	3	4	5	6	7	8																																																																																					
Drawing Number: ST-262 (3 of 3)		Scale: NTS@A3	Revision: P2	 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																						
FIRST FIX			INSTALLATION PHASE			PRE-COMMISSIONING																																																																																						
<table><tr><th colspan="2">TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>			TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>			TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	<u>CHECKLIST BEFORE COMMISSIONING</u> AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>				YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE																																																																																												
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																																											
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																																																											
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																																											
MIN FLOW RATE (l/min) DHW	28																																																																																											
MINIMUM WATER VOLUME (Litres)	20																																																																																											
MAX CURRENT (A)	30.8																																																																																											
FUSE (A)	32																																																																																											
MAINS FOR BUH (X9M)	230v																																																																																											
FUSE (A)	16																																																																																											
MAINS FOR DHW BSH (K3M)	230v																																																																																											
FUSE (A)	16																																																																																											
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																																											
MAXIMUM DISTANCE TO TANK (m)	10																																																																																											
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																											
HEIGHT (mm)	870																																																																																											
WIDTH (mm)	1380																																																																																											
DEPTH (mm)	460																																																																																											
WEIGHT EMPTY (kg)	149																																																																																											
WEIGHT FULL (kg)	157																																																																																											
TABLE 2 - INSULATION THICKNESS																																																																																												
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																											
<20	19																																																																																											
20-30	32																																																																																											
30-40	40																																																																																											
40-50	50																																																																																											
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																											
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																											
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																											
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																											
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																											
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																											
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																											
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																											
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																											
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																											
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																											
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																											
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																											
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																											
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																											
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																											
No top-side obstacle Suction-side obstacle 			 UNBOXING LARGE MONOBLOC SCAN ME  3-WAY VALVE EXPLAINED SCAN ME  MMI USER GUIDE SCAN ME  DAIKIN ALTHERMA LARGE MONOBLOC SCAN ME			<u>CHECKLIST DURING COMMISSIONING</u> <table><tr><td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>TO PERFORM AN AIR PURGE.</td></tr><tr><td></td><td>TO PERFORM A TEST RUN.</td></tr><tr><td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr><tr><td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr></table>				THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																										
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																											
	TO PERFORM AN AIR PURGE.																																																																																											
	TO PERFORM A TEST RUN.																																																																																											
	TO PERFORM AN ACTUATOR TEST RUN.																																																																																											
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																																																																											
NOTES - AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. - IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. - ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. - ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. - EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																												
<table><tr><td></td><td></td><td></td><td></td><td></td></tr><tr><td>P2</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>25.10.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>15.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>							P2	PHASE 2 UPDATES	PBM	SB	25.10.24	P1	PRELIMINARY ISSUE	RB	SB	15.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE) THIRD PARTY CYLINDER, DHW, AND RADIATORS		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk 																																																																
P2	PHASE 2 UPDATES	PBM	SB	25.10.24																																																																																								
P1	PRELIMINARY ISSUE	RB	SB	15.05.23																																																																																								
Rev	Description	Engineer	Checked	Date																																																																																								
1	2	3	4	5	6	7	8																																																																																					

ST 263: EDLA High Capacity Monobloc - Third Party Cylinder DHW & UFH - **Mechanical**




ST 263: EDLA High Capacity Monobloc - Third Party Cylinder DHW & UFH - **Electrical**




ST 263: EDLA High Capacity Monobloc - Third Party Cylinder DHW & UFH - Key Data

1		2		3		4		5		6		7		8																																	
Drawing Number: ST-263 (3 of 3)		Scale: NTS@ A3		Revision: P3		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																							
FIRST FIX		INSTALLATION PHASE						PRE-COMMISSIONING																																							
								CHECKLIST BEFORE COMMISSIONING																																							
								AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.																																							
								<table border="1"> <tr> <td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr> <tr> <td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr> <tr> <td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr> <tr> <td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr> <tr> <td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr> <tr> <td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr> <tr> <td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr> <tr> <td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr> <tr> <td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr> <tr> <td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr> <tr> <td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr> <tr> <td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr> <tr> <td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr> <tr> <td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr> <tr> <td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr> <tr> <td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr> </table>									YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																														
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																														
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																														
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																														
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																														
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																														
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																														
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																														
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																														
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																														
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																														
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																														
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																														
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																														
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																														
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																														
								CHECKLIST DURING COMMISSIONING																																							
								<table border="1"> <tr> <td></td><td>THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr> <tr> <td></td><td>TO PERFORM AN AIR PURGE.</td></tr> <tr> <td></td><td>TO PERFORM A TEST RUN.</td></tr> <tr> <td></td><td>TO PERFORM AN ACTUATOR TEST RUN.</td></tr> <tr> <td></td><td>UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.</td></tr> </table>									THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		TO PERFORM AN AIR PURGE.		TO PERFORM A TEST RUN.		TO PERFORM AN ACTUATOR TEST RUN.		UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																						
	THE MINIMUM FLOW RATE IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																														
	TO PERFORM AN AIR PURGE.																																														
	TO PERFORM A TEST RUN.																																														
	TO PERFORM AN ACTUATOR TEST RUN.																																														
	UNDER FLOOR SCREED DRY OUT FUNCTION. THE UNDER FLOOR SCREED DRY OUT FUNCTION IS STARTED IF NECESSARY.																																														


ST 266: EDLA High Capacity Monobloc - Third Party Controls, Third Party Cylinder, DHW, Radiators & UFH - **Mechanical**




ST 266: EDLA High Capacity Monobloc - Third Party Controls, Third Party Cylinder, DHW, Radiators & UFH - **Electrical**




ST 266: EDLA High Capacity Monobloc - Third Party Controls, Third Party Cylinder, DHW, Radiators & UFH - Key Data

1	2	3	4	5	6	7	8																																																			
Drawing Number: ST-266 (3 of 3)	Scale: NTS@ A3	Revision: P3	 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.	• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																						
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING																																																					
					CHECKLIST BEFORE COMMISSIONING																																																					
					AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.																																																					
<table><tr><th colspan="2">TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>		TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>		TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	THIRD PARTY TANK TECHNICAL REQUIREMENTS The specifier must take care to ensure that the cylinder is suitable for the heat pump application. Where a third party cylinder has been specified, Daikin strongly recommend that the specifier/installer checks the following points: • Cylinder has a dry pocket to accommodate the Daikin cylinder sensor (Diameter 8mm, minimum recommend depth 28mm). • The heat exchanger coil is suitably dimensioned for the heat input from the relevant heat pump. • The immersion heater is positioned above the indirect heating coil. • Insulation of tank and the standing heat loss meets the requirements of the current building regulations. • Cylinder has the following approvals: G3, Water Regulations, Building Regulations, CE marked.		
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE																																																										
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																									
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																									
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																									
MIN FLOW RATE (l/min) DHW	28																																																									
MINIMUM WATER VOLUME (Litres)	20																																																									
MAX CURRENT (A)	30.8																																																									
FUSE (A)	32																																																									
MAINS FOR BUH (X9M)	230v																																																									
FUSE (A)	16																																																									
MAINS FOR DHW BSH (K3M)	230v																																																									
FUSE (A)	16																																																									
MINIMUM CABLE (mm²) FOR MMI	0.75																																																									
MAXIMUM DISTANCE TO TANK (m)	10																																																									
MAXIMUM LEVEL DIFFERENCE (m)	5																																																									
HEIGHT (mm)	870																																																									
WIDTH (mm)	1380																																																									
DEPTH (mm)	460																																																									
WEIGHT EMPTY (kg)	149																																																									
WEIGHT FULL (kg)	157																																																									
TABLE 2 - INSULATION THICKNESS																																																										
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																									
<20	19																																																									
20-30	32																																																									
30-40	40																																																									
40-50	50																																																									
		 UNBOXING LARGE MONOBLOC		 3-WAY VALVE EXPLAINED																																																						
		 MMI USER GUIDE		 DAIKIN ALTHERMA LARGE MONOBLOC																																																						
NOTES																																																										
• AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. • IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. • ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. • ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. • EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. • FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																										
<table><tr><td>P3</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>28.08.24</td></tr><tr><td>P2</td><td>MIXING VALVE UPDATED</td><td>PBM</td><td>SB</td><td>27.03.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>		P3	PHASE 2 UPDATES	PBM	SB	28.08.24	P2	MIXING VALVE UPDATED	PBM	SB	27.03.24	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE) THIRD PARTY CYLINDER, THIRD PARTY CONTROLS, DHW, RADIATORS & UFH		Drawing Status: PRELIMINARY																																
P3	PHASE 2 UPDATES	PBM	SB	28.08.24																																																						
P2	MIXING VALVE UPDATED	PBM	SB	27.03.24																																																						
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																						
Rev	Description	Engineer	Checked	Date																																																						
				Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																						
1	2	3	4	5	6	7	8																																																			

ST 268: EDLA High Capacity Monobloc - Third Party Cylinder DHW, Radiators & UFH - **Mechanical**




ST 268: EDLA High Capacity Monobloc - Third Party Cylinder DHW, Radiators & UFH - **Electrical**




ST 268: EDLA High Capacity Monobloc - Third Party Cylinder DHW, Radiators & UFH - Key Data

1	2	3	4	5	6	7	8																																																																																
Drawing Number: ST-268 (3 of 3)		Scale: NTS@ A3	Revision: P1	• SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																																																	
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING																																																																																		
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		TABLE 2 - INSULATION THICKNESS			CHECKLIST BEFORE COMMISSIONING																																																																																		
<table><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>			PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED. <table><tr><td></td><td>YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.</td></tr><tr><td></td><td>THE OUTDOOR UNIT IS PROPERLY MOUNTED.</td></tr><tr><td></td><td>FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.</td></tr><tr><td></td><td>THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.</td></tr><tr><td></td><td>THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.</td></tr><tr><td></td><td>THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.</td></tr><tr><td></td><td>THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.</td></tr><tr><td></td><td>ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.</td></tr><tr><td></td><td>ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.</td></tr><tr><td></td><td>THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.</td></tr><tr><td></td><td>THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.</td></tr><tr><td></td><td>THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.</td></tr><tr><td></td><td>FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.</td></tr><tr><td></td><td>THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.</td></tr><tr><td></td><td>THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.</td></tr><tr><td></td><td>(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.</td></tr></table>				YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.		THE OUTDOOR UNIT IS PROPERLY MOUNTED.		FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.		THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.		THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.		THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.		THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.		ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.		ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.		THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.		THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.		THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.		FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.		THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.		THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.		(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																																						
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																																																						
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																																						
MIN FLOW RATE (l/min) DHW	28																																																																																						
MINIMUM WATER VOLUME (Litres)	20																																																																																						
MAX CURRENT (A)	30.8																																																																																						
FUSE (A)	32																																																																																						
MAINS FOR BUH (X9M)	230v																																																																																						
FUSE (A)	16																																																																																						
MAINS FOR DHW BSH (K3M)	230v																																																																																						
FUSE (A)	16																																																																																						
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																																						
MAXIMUM DISTANCE TO TANK (m)	10																																																																																						
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																																						
HEIGHT (mm)	870																																																																																						
WIDTH (mm)	1380																																																																																						
DEPTH (mm)	460																																																																																						
WEIGHT EMPTY (kg)	149																																																																																						
WEIGHT FULL (kg)	157																																																																																						
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																																						
<20	19																																																																																						
20-30	32																																																																																						
30-40	40																																																																																						
40-50	50																																																																																						
	YOU READ THE COMPLETE INSTALLATION INSTRUCTIONS, AS DESCRIBED IN THE INSTALLER REFERENCE GUIDE.																																																																																						
	THE OUTDOOR UNIT IS PROPERLY MOUNTED.																																																																																						
	FIELD WIRING - BE SURE THAT THE FIELD WIRING HAS BEEN CARRIED OUT ACCORDING TO THE INSTRUCTIONS DESCRIBED IN THE CHAPTER '6 ELECTRICAL INSTALLATION', ACCORDING TO THE WIRING DIAGRAMS AND ACCORDING TO THE APPLICABLE LEGISLATION.																																																																																						
	THE SYSTEM IS PROPERLY EARTHED AND EARTH TERMINALS ARE TIGHTENED.																																																																																						
	THE FUSES OR LOCALLY INSTALLED PROTECTION DEVICES ARE INSTALLED ACCORDING TO THIS DOCUMENT, AND HAVE NOT BEEN BYPASSED.																																																																																						
	THE POWER SUPPLY VOLTAGE MATCHES THE VOLTAGE ON THE IDENTIFICATION LABEL OF THE UNIT.																																																																																						
	THERE ARE NO DAMAGED COMPONENTS OR SQUEEZED PIPES ON THE INSIDE OF THE DOOR UNIT.																																																																																						
	ONLY FOR MODELS WITH INTEGRATED BACK UP HEATER (F1B:FIELD SUPPLY) OR IF THE EXTERNAL BACK UP HEATER KIT (F1B: FACTORY MOUNTED IN THE BACK UP HEATER KIT) IS INSTALLED: BACK UP HEATER CIRCUIT BREAKER F1B IS TURNED ON.																																																																																						
	ONLY FOR TANKS WITH BUILT-IN BOOSTER HEATER: BOOSTER HEATER CIRCUIT BREAKER F2B (FIELD SUPPLY) IS TURNED ON.																																																																																						
	THE CORRECT PIPE SIZE IS INSTALLED AND THE PIPES ARE PROPERLY INSULATED.																																																																																						
	THERE ARE NO WATER LEAKS INSIDE THE OUTDOOR UNIT.																																																																																						
	THE SHUT OFF VALVES ARE PROPERLY INSTALLED AND FULLY OPEN.																																																																																						
	FOR MODELS WITH INTEGRATED BACK UP HEATER: THE AUTOMATIC AIR PURGE VALVE (ON THE BACK UP HEATER) IS OPEN. FOR OTHER MODELS: THE MANUAL AIR PURGE VALVE IS CLOSED.																																																																																						
	THE PRESSURE RELIEF VALVE PURGES WATER WHEN OPENED. CLEAN WATER MUST COME OUT.																																																																																						
	THE MINIMUM WATER VOLUME IS GUARANTEED IN ALL CONDITIONS. SEE 'TO CHECK THE WATER VOLUME AND FLOW RATE' IN '5.1 PREPARING WATER PIPING'.																																																																																						
	(IF APPLICABLE) THE DOMESTIC HOT WATER TANK IS FILLED COMPLETELY.																																																																																						
NOTES - AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. - IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. - ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. - ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. - EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. - FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																																							
1		2		3		4																																																																																	
P1 PRELIMINARY ISSUE		PBM SB 06.09.2024		1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE) THIRD PARTY CYLINDER, THIRD PARTY CONTROLS, DHW & 2 ZONE RADIATOR CIRCUITS																																																																																	
Rev Description		Engineer Checked Date		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																																																																	
1		2		3		4																																																																																	


ST 279: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder & Third Party Controls DHW, 2 Zone Radiators - **Mechanical**




ST 279: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder & Third Party Controls DHW, 2 Zone Radiators - **Electrical**



ST 282: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder DHW & Radiators - **Mechanical**




ST 282: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder DHW & Radiators - **Electrical**




ST 282: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder DHW & Radiators - Key Data

1	2	3	4	5	6	7	8																																																				
Drawing Number: ST-282 (3 of 3)		Scale: NTS@ A3	Revision: P2	SEE PAGE 1 FOR MECHANICAL SET UP. SEE PAGE 2 FOR DETAILED WIRING. SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING OPTIONAL FOR HEAT METERS ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																					
FIRST FIX		INSTALLATION PHASE			PRE-COMMISSIONING																																																						
					CHECKLIST BEFORE COMMISSIONING																																																						
					AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.																																																						
<table><tr><th colspan="2">TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>		TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>			TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50			
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE																																																											
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																										
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																										
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																										
MIN FLOW RATE (l/min) DHW	28																																																										
MINIMUM WATER VOLUME (Litres)	20																																																										
MAX CURRENT (A)	30.8																																																										
FUSE (A)	32																																																										
MAINS FOR BUH (X9M)	230v																																																										
FUSE (A)	16																																																										
MAINS FOR DHW BSH (K3M)	230v																																																										
FUSE (A)	16																																																										
MINIMUM CABLE (mm²) FOR MMI	0.75																																																										
MAXIMUM DISTANCE TO TANK (m)	10																																																										
MAXIMUM LEVEL DIFFERENCE (m)	5																																																										
HEIGHT (mm)	870																																																										
WIDTH (mm)	1380																																																										
DEPTH (mm)	460																																																										
WEIGHT EMPTY (kg)	149																																																										
WEIGHT FULL (kg)	157																																																										
TABLE 2 - INSULATION THICKNESS																																																											
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																										
<20	19																																																										
20-30	32																																																										
30-40	40																																																										
40-50	50																																																										
		OVERVIEW OF PRE-PLUMBED CYLINDER WIRING CONNECTIONS																																																									
		<table><tr><td>CABLE SECTION 2.5mm²</td></tr><tr><td>MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M</td></tr><tr><td>CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.</td></tr><tr><td>CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA</td></tr><tr><td>MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M</td></tr><tr><td>THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK</td></tr></table>			CABLE SECTION 2.5mm²	MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M	CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.	CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA	MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M	THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK																																																	
CABLE SECTION 2.5mm²																																																											
MINIMUM CABLE SECTION 0.75mm; MAXIMUM LENGTH 20M																																																											
CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 500M. APPLICABLE FOR BOTH SINGLE USER INTERFACE AND DUAL USE INTERFACE CONNECTION.																																																											
CABLE SECTION 0.75mm² TO 1.25mm²; MAXIMUM LENGTH 50M. VOLTAGE-FREE CONTACT SHALL ENSURE THE MINIMUM APPLICABLE LOAD OF 15 V DC, 10MA																																																											
MINIMUM CABLE SECTION 0.75mm²; MAXIMUM LENGTH 10M																																																											
THE THERMISTOR AND CONNECTION WIRE 12M ARE PRE-INSTALLED ON THE DOMESTIC HOT WATER TANK																																																											
No top-side obstacle Suction-side obstacle		 UNBOXING LARGE MONOBLOC 3-WAY VALVE EXPLAINED MMI USER GUIDE DAIKIN ALTHERMA LARGE MONOBLOC																																																									
NOTES																																																											
AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																											
<table><tr><td>P2</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>08.09.24</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>		P2	PHASE 2 UPDATES	PBM	SB	08.09.24	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS. 2. WORK TO FIGURED DIMENSIONS ONLY. 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE) PRE-PLUMBED CYLINDER, DOMESTIC HOT WATER & RADIATORS		Drawing Status: PRELIMINARY		Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																																				
P2	PHASE 2 UPDATES	PBM	SB	08.09.24																																																							
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																							
Rev	Description	Engineer	Checked	Date																																																							
1	2	3	4	5	6	7	8																																																				


ST 283: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder DHW & UFH - **Mechanical**




ST 283: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder DHW & UFH - **Electrical**




ST 286: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder & Third Party Controls DHW, Radiators & UFH - **Mechanical**



ST 286: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder & Third Party Controls DHW, Radiators & UFH - **Electrical**



ST 286: EDLA High Capacity Monobloc - Pre-Plumbed Cylinder & Third Party Controls DHW, Radiators & UFH - Key Data

1		2		3		4		5		6		7		8																																																									
Drawing Number: ST-286 (3 of 3)				Scale: NTS@ A3		Revision: P4		 • SEE PAGE 1 FOR MECHANICAL SET UP. • SEE PAGE 2 FOR DETAILED WIRING. • SEE PAGE 3 FOR RELEVANT CONTROLLER SYSTEMS CONFIGURATION SETTINGS.		• DPDT RELAY (NOT SUPPLIED BY DAIKIN) SEE PAGE 2 FOR DETAILED WIRING • OPTIONAL FOR HEAT METERS • ROTARY ISOLATOR TO BE SITUATED OUTSIDE PROTECTIVE ZONE.																																																													
FIRST FIX								INSTALLATION PHASE				PRE-COMMISSIONING																																																											
												CHECKLIST BEFORE COMMISSIONING																																																											
												AFTER THE INSTALLATION OF THE UNIT, FIRST CHECK THE ITEMS LISTED BELOW. ONCE ALL CHECKS ARE FULFILLED, THE UNIT MUST BE CLOSED. POWER-UP THE UNIT AFTER IT IS CLOSED.																																																											
<table><tr><th colspan="2">TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE</th></tr><tr><th>EQUIPMENT</th><th>EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3</th></tr><tr><td>PRIMARY PIPEWORK (mm)</td><td>MINIMUM 28mm</td></tr><tr><td>NOMINAL FLOW RATE (l/min) CENTRAL HEATING</td><td>22</td></tr><tr><td>MIN FLOW RATE (l/min) DHW</td><td>28</td></tr><tr><td>MINIMUM WATER VOLUME (Litres)</td><td>20</td></tr><tr><td>MAX CURRENT (A)</td><td>30.8</td></tr><tr><td>FUSE (A)</td><td>32</td></tr><tr><td>MAINS FOR BUH (X9M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MAINS FOR DHW BSH (K3M)</td><td>230v</td></tr><tr><td>FUSE (A)</td><td>16</td></tr><tr><td>MINIMUM CABLE (mm²) FOR MMI</td><td>0.75</td></tr><tr><td>MAXIMUM DISTANCE TO TANK (m)</td><td>10</td></tr><tr><td>MAXIMUM LEVEL DIFFERENCE (m)</td><td>5</td></tr><tr><td>HEIGHT (mm)</td><td>870</td></tr><tr><td>WIDTH (mm)</td><td>1380</td></tr><tr><td>DEPTH (mm)</td><td>460</td></tr><tr><td>WEIGHT EMPTY (kg)</td><td>149</td></tr><tr><td>WEIGHT FULL (kg)</td><td>157</td></tr></table>								TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE		EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3	PRIMARY PIPEWORK (mm)	MINIMUM 28mm	NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22	MIN FLOW RATE (l/min) DHW	28	MINIMUM WATER VOLUME (Litres)	20	MAX CURRENT (A)	30.8	FUSE (A)	32	MAINS FOR BUH (X9M)	230v	FUSE (A)	16	MAINS FOR DHW BSH (K3M)	230v	FUSE (A)	16	MINIMUM CABLE (mm²) FOR MMI	0.75	MAXIMUM DISTANCE TO TANK (m)	10	MAXIMUM LEVEL DIFFERENCE (m)	5	HEIGHT (mm)	870	WIDTH (mm)	1380	DEPTH (mm)	460	WEIGHT EMPTY (kg)	149	WEIGHT FULL (kg)	157	<table><tr><th colspan="2">TABLE 2 - INSULATION THICKNESS</th></tr><tr><th>PIPING LENGTH (m)</th><th>MINIMUM INSULATION THICKNESS (mm)</th></tr><tr><td><20</td><td>19</td></tr><tr><td>20-30</td><td>32</td></tr><tr><td>30-40</td><td>40</td></tr><tr><td>40-50</td><td>50</td></tr></table>								TABLE 2 - INSULATION THICKNESS		PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)	<20	19	20-30	32	30-40	40	40-50	50	OVERVIEW OF PRE-PLUMBED CYLINDER WIRING CONNECTIONS			
TABLE - DATA - MonoBloc HEATING ONLY 1 PHASE																																																																							
EQUIPMENT	EDLA09D3V3 / EDLA11D3V3 / EDLA14D3V3 / EDLA16D3V3																																																																						
PRIMARY PIPEWORK (mm)	MINIMUM 28mm																																																																						
NOMINAL FLOW RATE (l/min) CENTRAL HEATING	22																																																																						
MIN FLOW RATE (l/min) DHW	28																																																																						
MINIMUM WATER VOLUME (Litres)	20																																																																						
MAX CURRENT (A)	30.8																																																																						
FUSE (A)	32																																																																						
MAINS FOR BUH (X9M)	230v																																																																						
FUSE (A)	16																																																																						
MAINS FOR DHW BSH (K3M)	230v																																																																						
FUSE (A)	16																																																																						
MINIMUM CABLE (mm²) FOR MMI	0.75																																																																						
MAXIMUM DISTANCE TO TANK (m)	10																																																																						
MAXIMUM LEVEL DIFFERENCE (m)	5																																																																						
HEIGHT (mm)	870																																																																						
WIDTH (mm)	1380																																																																						
DEPTH (mm)	460																																																																						
WEIGHT EMPTY (kg)	149																																																																						
WEIGHT FULL (kg)	157																																																																						
TABLE 2 - INSULATION THICKNESS																																																																							
PIPING LENGTH (m)	MINIMUM INSULATION THICKNESS (mm)																																																																						
<20	19																																																																						
20-30	32																																																																						
30-40	40																																																																						
40-50	50																																																																						
								 UNBOXING LARGE MONOBLOC								 3-WAY VALVE EXPLAINED																																																							
								 MMI USER GUIDE				 DAIKIN ALTHERMA LARGE MONOBLOC																																																											
NOTES																																																																							
- AFTER REMOVING THE AIR, AUTOMATIC AIR VENT(S) MUST BE OPEN. - IF GLYCOL IS BEING ADDED TO THE SYSTEM THEN ANTI-FREEZE VALVES MUST NOT BE INSTALLED HOWEVER, ADDITIONAL FLOW SWITCH (EKFLSW1) MUST BE PURCHASE AND INSTALLED IN THE UNIT. - ISOLATION VALVES AND FLUSHING BYPASS CIRCUIT ARE RECOMMENDED FOR THE OUTDOOR UNIT. FLOW ISOLATION VALVE REQUIRED ON OUTDOOR UNIT (SUPPLIED BY OTHERS). DO NOT PRESSURE TEST OR FLUSH THROUGH THE DAIKIN UK EQUIPMENT. - ALL ELECTRICAL WORKS MUST BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT VERSION OF BS7671 AND ANY LOCAL LEGISLATION'S. - EARTH LEAKAGE DETECTION DEVICE IS REQUIRED, THIS MUST BE INVERTER TOLERANT AND RATED AT 30MA. - FOR ADDITIONAL INFORMATION PLEASE REFER TO THE INSTALLER REFERENCE GUIDE (IRG DOWNLOADABLE FROM DAIKIN UK MY.DAIKIN.CO.UK)																																																																							
F																																																																							
<table><tr><td>P4</td><td>PHASE 2 UPDATES</td><td>PBM</td><td>SB</td><td>28.08.24</td></tr><tr><td>P3</td><td>MIXING VALVE UPDATED</td><td>PBM</td><td>SB</td><td>26.03.24</td></tr><tr><td>P2</td><td>WIRING UPDATED</td><td>PBM</td><td>SB</td><td>20.10.23</td></tr><tr><td>P1</td><td>PRELIMINARY ISSUE</td><td>RB</td><td>SB</td><td>16.05.23</td></tr><tr><td>Rev</td><td>Description</td><td>Engineer</td><td>Checked</td><td>Date</td></tr></table>				P4	PHASE 2 UPDATES	PBM	SB	28.08.24	P3	MIXING VALVE UPDATED	PBM	SB	26.03.24	P2	WIRING UPDATED	PBM	SB	20.10.23	P1	PRELIMINARY ISSUE	RB	SB	16.05.23	Rev	Description	Engineer	Checked	Date	<table><tr><td colspan="2">1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.</td></tr><tr><td colspan="2">2. WORK TO FIGURED DIMENSIONS ONLY.</td></tr><tr><td colspan="2">3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.</td></tr></table>				1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.		2. WORK TO FIGURED DIMENSIONS ONLY.		3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.		Drawing: MonoBloc EDLA 09-16 (1 PHASE) PRE-PLUMBED CYLINDER, THIRD PARTY CONTROLS, DHW, RADIATORS & UFH				Drawing Status: PRELIMINARY				Telephone: 01932 879 070 (Option 1) Email: heating@daikin.co.uk																								
P4	PHASE 2 UPDATES	PBM	SB	28.08.24																																																																			
P3	MIXING VALVE UPDATED	PBM	SB	26.03.24																																																																			
P2	WIRING UPDATED	PBM	SB	20.10.23																																																																			
P1	PRELIMINARY ISSUE	RB	SB	16.05.23																																																																			
Rev	Description	Engineer	Checked	Date																																																																			
1. THE COPYRIGHT OF THIS DRAWING IS VESTED IN DAIKIN UK AND IT MAY NOT BE REPRODUCED IN WHOLE OR PART OR USED FOR THE MANUFACTURE OF ANY ARTICLE WITHOUT THE EXPRESS PERMISSION OF THE COPYRIGHT HOLDERS.																																																																							
2. WORK TO FIGURED DIMENSIONS ONLY.																																																																							
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S, SERVICE ENGINEER'S AND DAIKIN UK DRAWINGS AND SPECIFICATIONS.																																																																							

Warranty and maintenance

Extended end user warranty available

In the unlikely event that a heat pump fails, then Daikin will fix the system at no cost to the householder, if it is covered by our end user warranty.

Daikin systems come with an extended end user warranty, as long as they are registered by the installer on Stand By Me.

For full Terms and Conditions of the warranty policy please go to:

www.daikin.co.uk/en_gb/residential/services/warranty/warranty-policies.html
or Stand By Me.


Registering warranties

Once the system has been successfully installed, please complete the commissioning details on Stand By Me so that your householder can benefit from our end user equipment warranty.



Daikin e-Care

Download the app now to access registration, commissioning, configuration and trouble shooting on both Apple Store and Google Play.



Warranty support

In the event of a fault, it is important to first identify the issue before making a Warranty Claim.

To diagnose an equipment fault, the householder may contact any of the following to identify the reasons for the fault:

- The original installer
- A Daikin-trained installer
- Daikin UK

If the householder would like us to visit and identify reasons for the fault, we will charge for any reasonable costs incurred where no fault is found with the product.

All visits by Daikin UK that are related to the installation or external system faults will be charged to the householder. For these reasons, the original installer may first wish to visit and verify the possible reasons for the fault to ensure that there are no system related faults.


To arrange the warranty visit, the householder should contact us with full details of the fault including the serial number. Please note that the householder will be responsible for any costs if we need to arrange any special equipment to access the installation, e.g. wall mounted outdoor units, or indoor units installed in lofts.

Maintenance packages

Daikin UK offers homeowners maintenance packages for Daikin Altherma and Hybrid systems. Visit Stand By Me to purchase your maintenance package.

For more information on our maintenance packages please visit
www.daikin.co.uk/en_gb/residential/services/maintenance.html

Visit **Stand By Me** today to complete your system registration, claim your FREE extended warranty and explore and purchase your maintenance packages.



daikin.co.uk

National Heating Installer Hub: 01932 879070

Daikin Helpdesk 01932 879277

The present brochure is drawn up by way of information only and does not constitute an offer binding upon Daikin UK. Daikin UK has compiled the content of this brochure to the best of its knowledge. No express or implied warranty is given for the completeness, accuracy, reliability or fitness for particular purpose of its content and the products and services presented therein. Specifications are subject to change without prior notice. Daikin UK explicitly rejects any liability for any direct or indirect damage, in the broadest sense, arising from or related to the use and/or interpretation of this brochure. All content is copyrighted by Daikin UK.

Daikin Airconditioning UK Limited The Heights Brooklands Weybridge Surrey KT13 0NY Tel 01932 879000 daikin.co.uk

